



The Head Office,
People's Primary Healthcare Initiative, Balochistan.
Admin Section
Ref No. PPHI-B/H.O-BLN/CW/2026/06
Dated: _____

Technical Proposal

People's Primary Healthcare Initiative (PPHI) - Balochistan

**TENDER DOCUMENT FOR MAJOR AND MINOR CIVIL WORKS OF BASIC
HEALTH UNITS (BHUs) OF PPHI-BALUCHISTAN – DISTRICT PISHIN, 2026**

NAME OF BIDDER: _____
(To be filled-in by the Bidder)

Address: People's Primary Healthcare Initiative (PPHI) - Balochistan
House # 8-A, Jinnah Town, Samungli Road, Quetta-Pakistan.

Phone: 081-2863620
Website: www.pphib.org

LETTER OF INVITATION FOR BIDS:

Sealed proposals are invited from eligible bidders for major and minor civil works at (04) four BHUs of PPHI-Balochistan, under the People's Primary Healthcare Initiative (PPHI)-Balochistan in accordance with the applicable procurement rules and policies of PPHI-Balochistan. Firms having proven experience in the execution of major and minor civil works and construction also duly registered with the Pakistan Engineering Council (PEC) under the relevant categories and codes are eligible to participate in the bidding process.

REQUIRED BIDDING INFORMATION	TO BE FILLED BY THE PEOPLES PRIMARY HEALTHCARE INITIATIVE (PPHI-B)
DESIGNATION OF PROCUREMENT OFFICER	MANAGER ADMIN
POSTAL ADDRESS OF THE PEOPLE'S PRIMARY HEALTH CARE INITIATIVE (PPHI-BALOCHISTAN)	HOUSE # 8-A, JINNAH TOWN SAMUNGLI ROAD, QUETTA-PAKISTAN.
PHONE NUMBER & FAX NUMBER	081-2863620 & 081-2863623
E-MAIL ADDRESS & WEBSITE	E-mail: PPHIBLN@GMAIL.COM Website: https://www.pphib.org
METHOD OF PROCUREMENT	SINGLE STAGE - TWO ENVELOPE BIDDING PROCEDURE
PRE-BID MEETING	DATE: 20 JULY 2026 AT 2:00PM , PPHI-B HEAD OFFICE, 8-A JINNAH TOWN, SAMSUNG LI ROAD, QUETTA. ALL COMPETITIVE BIDDERS ARE REQUESTED TO ATTEND THE PRE BID MEETING.
ISSUANCE OF BIDDING DOCUMENTS	The tender documents can be downloaded from the PPHI-Balochistan website: http://pphib.org/
DEADLINE FOR SUBMISSION OF BIDS	Date: 30 JULY 2026 & Till 11:00 A.M directly submitted to the Head Office, PPHI-Balochistan.
OPENING OF TECHNICAL BIDS	Date: 30 JULY 2026 & Time 12:00 P.M at the Head Office of PPHI-Balochistan.
OPENING OF FINANCIAL BIDS	Date: Shall be communicated to qualified bidders after technical evaluation.
BIDDING DOCUMENT FEE	AMOUNT: PKR. 2,000/- PAY ORDER IN THE NAME OF PPHI- Balochistan WITH TECHNICAL BID IN A SEPARATE ENVELOPE. SUBMISSION OF BIDDING DOCUMENT FEE IS MANDATORY WITH TECHNICAL PROPOSAL,
BID SECURITY/EARNEST MONEY	AMOUNT: 2% OF THE QUOTED AMOUNT MANNER OF <u>CALL DEPOSIT/ PAY ORDER</u> IN FAVOR OF PPHI-BALOCHISTAN , MUST BE PART OF FINANCIAL PROPOSAL.

ELIGIBILITY CRITERIA FOR BIDDERS:

SR. NO	BIDDERS ELIGIBILITY FACTOR	MANDATORY REQUIREMENT	DOCUMENT REQUIRED
01	Legal Status & Tax Registration.	The bidder must possess a valid NTN Certificate, be registered with the Federal Board of Revenue (FBR) under the relevant tariff/registration category for Construction / Civil Works / Government Contractors, and must be an Active Taxpayer at the time of submission of bid documents.	Copies of valid NTN Certificate, GST & BSTS Registration Certificate (Where applicable), and Active Taxpayer Profile, duly verifiable from FBR IRIS / official FBR and BRA website.
02	Relevant Experience	Minimum 03 (Three) successfully completed similar Civil Work assignments, having cumulative value not less than PKR. 05 million, during the last Three (03) Years. (FY 2023, 2024, and 2025.)	Copies of Work Orders and Completion Certificates, clearly mentioning scope, value, and dates, duly attested by Senior Executive of the firm. PPHI-B reserve the right of verification of work orders, completion certificates.
03	Financial Capacity (For Firms)	Minimum average annual turnover of PKR 10 million during the last three (03) financial years (FY 2023, 2024, and 2025), supported by audited financial statements or Annual tax returns.	Audited Financial Statements OR Annual Income Tax Return only.
04	Non-Blacklisting and disclosure of litigation cases	Must not be presently black-listed by any Government/ Semi Govt or Private Organization must declare the litigation cases.	Declaration of Non-blacklisting and disclosure of litigation cases on Non-Judicial Stamp paper by the Bidder/Individual.
05	PEC Registration	The bidder must be registered with the Pakistan Engineering Council (PEC) in an appropriate category and specialization relevant to the scope of civil works (e.g., C-6, C-5 or above). Registration must be valid at the time of bid submission.	Copy of valid PEC Registration Certificate clearly showing category, specialization, and validity.
06	Technical Capacity	Technical HR (Engineers) with previous experience of similar assignments as required by the Peoples Primary Health Care Initiative (PPHI-B) in the Data-sheet	Detailed CVs of the HR/Individual along with PEC registration. 01 Civil Engineer(PEC Registered) 01 Site Supervisor.
07	Work completion compliance	Must agree to serve the Contract within agreed time i.e., 90 days.	Completion time must be clearly specified in the Technical Bid.
08	Agreement with all the terms & conditions	Must unconditionally agree with all the instructions, terms & conditions specified in the bidding documents & contract agreement	Signature & company seal on every page of the bidding document.
09	Submission of Bidding Document Fee & Bid Security	As required by the People's Primary Healthcare Initiative (PPHI-Balochistan) in the Tender Notice.	AMOUNT: PKR. 2,000/- Tender Fee in separate envelope with technical proposal. AMOUNT: 2 % Security deposit with financial proposal Only.

NOTE:

- a) It is mandatory for the bidders to score "YES" in all the above-mentioned nine (09) requirements of eligibility. In case of single "NO" to any requirement, the Bid shall be declared NON-RESPONSIVE resulting disqualification for sample submission and financial bid opening.
- b) No document shall be added in bidding documents once bid documents are submitted.
- c) Submission of Multiple Bids under a Single Firm (Lot-wise):
 - i. A Single Bidders may be awarded multiple lots, subject to fulfillment of technical and financial qualification criteria.
 - ii. Each bid shall complete in all respects and shall be submitted separately, including independent Technical and Financial Proposals along with a separate Call Deposit Receipt (CDR)/Bid Security for each lot. Partial bidding within a lot or submission of incomplete bids shall render the bid non-responsive.
- d) Please avoid to attach documents not required in the above mentioned criteria and it would be convenient to tag each eligibility criteria documents.
- e) Bidders from other cities/provinces may send their bids via courier at below mentioned mailing address and can participate in the bidding process virtually through online link (subject to prior intimation to the procuring officer) if desired, otherwise physical presence is preferred.
- f) Technical proposals shall not contain any financial proposal information; otherwise the bid shall be rejected.
- g) The Procuring Agency reserves the right to reject any or all bids or cancel the procurement proceedings at any time prior to award of contract without disclosing any reason.

Postal Address: PPHI-B Head Office House # 8-A, Jinnah Town, Samungli Road, Quetta.

Bidding Instructions and General Conditions

1. Bid Submission Requirements

- a) The bidder must quote for the entire scope of works or lot wise specified in the tender document. Partial, conditional, or incomplete bids shall be rejected.
- b) All bids must be tape-bound, properly sealed, and clearly labeled. Each page must be numbered, signed, and stamped by the authorized representative of the firm.
- c) All documents shall be attached in the sequence prescribed in the tender document for evaluation purposes.
- d) Any interlineations, erasers, or overwriting shall be valid only if initialized by the person(s) signing the bid.
- e) Blank fields in the bid forms must be duly filled. Incomplete or unsigned bids shall be treated as non-responsive.

2. Method and Deadline of Submission

- a) Preferably, bids shall be submitted by hand through the firm's authorized representative on or before the date and time specified in the Letter of Invitation.
- b) The bid shall comprise a single package containing two separate envelopes:
 - a. Technical Proposal
 - b. Financial Proposal
- c) Each envelope shall be sealed and marked in bold letters as "TECHNICAL PROPOSAL" and "FINANCIAL PROPOSAL" (in case of bidding for more than one lot)
- d) Both envelopes shall then be placed in an outer sealed envelope clearly marked with the Tender Reference Number and Subject.
- e) Bids received after the specified deadline shall be rejected without opening.

3. Conditions for Opening and Validity

- a) If the submission or opening date falls on a public holiday or non-working day, the bids shall be opened on the next working day at the same time and venue.
- b) A bidder may withdraw its bid before the submission deadline.
 - I. No withdrawal is permitted after the submission deadline until the expiry of the bid validity period.
 - II. Any withdrawal during the validity period at any stage may lead to legal action under applicable rules of PPHI-B.

4. Eligibility of Bidders

- a) The invitation is open to all firms registered with the Federal Board of Revenue (FBR) under the relevant registration/tariff category for Construction / Civil Works / Government Contractors, subject to fulfillment of all mandatory eligibility criteria.
- b) Bidders must have demonstrated experience in the execution and completion of major and/or minor civil works for government, semi-government, institutional, or similar organizations.
- c) Bidders under declaration of ineligibility, suspension, or blacklisting by any government, regulatory authority, or other organization are not eligible to participate.

5. Blacklisting and Debarment

The following actions shall render a bidder liable for blacklisting/debarment:

- a) Submission of false, fabricated, or forged documents or misrepresentation of facts at any stage of the bidding or contract execution.
- b) Failure to execute the civil works in accordance with the approved drawings, technical specifications, quality standards, BOQs, or agreed completion schedule.
- c) Persistent non-compliance with contract terms or specifications.
- d) Engagement in corrupt, fraudulent, or unethical practices.
- e) Bid rigging, tender fixing, or any conduct detrimental to the integrity and transparency of the procurement process.
- f) Any security-related concerns or actions that adversely affect the reputation of the Procuring Agency or the State.

6. Clarifications and Amendments

- a) A prospective bidder may seek clarification(s) in writing not later than seven (7) days prior to the submission deadline at the Procuring Agency's address indicated in the Bid Data Sheet.
- b) The Procuring Agency shall issue written responses (without disclosing the identity of the inquirer) to all bidders who have obtained the documents no verbal response shall be accepted.
- c) The Procuring Agency may, at any time before the submission deadline, amend the bidding documents through a written addendum.
- d) Such amendments shall be notified through official correspondence or publication at the official PPHI-B website.
- e) To accommodate the amendment(s), the Procuring Agency may extend the bid submission deadline, if deemed necessary.

7. Corrupt or Fraudulent Practices and Mechanism for Debarment / Blacklisting

A. Definition of Corrupt and Fraudulent Practices

For the purpose of this tender, the following practices shall constitute corrupt, fraudulent, coercive, collusive, or obstructive behavior, which are strictly prohibited:

- a) **Corrupt Practice:** Offering, giving, receiving, or soliciting directly or indirectly anything of value to influence the actions of a public official, procuring entity, or any party in the procurement process or contract execution for wrongful gain.
- b) **Fraudulent Practice:** Any act, omission, or misrepresentation that knowingly or recklessly misleads or attempts to mislead another party to obtain undue advantage or avoid an obligation.
- c) **Collusive Practice:** Any agreement or arrangement between two or more parties designed to establish bid prices at non-competitive, artificial levels to the detriment of fair competition.
- d) **Coercive Practice:** Direct or indirect actions, threats, or harm to any party or its property to improperly influence their participation or decisions in the procurement process.
- e) **Obstructive Practice:** Deliberate acts intended to impede investigation or audit processes, including falsifying or concealing evidence, making false statements, or intimidating witnesses.

8. Bid Price

- a) **Price Indication:** The bidder shall indicate, in the prescribed form, the unit rates (where applicable), BOQ rates, and the total bid price.

- b) **Completion and Authentication:** The Bill of Quantities (BOQ) and price schedules must be carefully filled, preferably typed, and signed and stamped on each page by the authorized representative of the bidder.
- c) **Compliance with Technical Specifications:** Bids must comply with all approved drawings, technical specifications, and BOQ requirements. Any deviation shall render the bid non-responsive.
- d) **Inclusive Pricing:** Prices must be quoted on a complete execution basis and shall include all applicable taxes, duties, levies, transportation, site establishment, tools and incidental costs necessary for execution of the works at the designated BHUs of PPHI-Balochistan.
- e) **Tax Exemptions:** Any exemption or reduction in taxes or duties available under law shall be passed on to the Procuring Agency.
- f) **Total Service Requirement:** Prices must be quoted for the entire scope of civil works of each lot as defined in the tender documents. Partial, conditional, or incomplete offers shall be considered non-responsive and rejected.

9. Bid Security

The bidder shall submit a bid security amount equal to 2% of the total quoted bid price for each lot, in favor of PPHI-Balochistan. The bid security shall be submitted as part of the Financial Bid only.

10. Bid Validity

- a. Bids shall remain valid for 90 days from the date of opening of bid.
- b. Bidders agreeing to extend validity must not change the substance of their bids.
- c. Bidders declining to extend may withdraw without forfeiting bid security.

Bidders who:-

- a) Agree to the Procuring Agency's request for extension of bid validity period shall not be permitted to change the substance of their bids; and
- b) Do not agree to an extension of the bid validity period shall be allowed to withdraw their bids without forfeiture of their bid securities.

11. Sub-Contracting, Subletting Clause

The bidder shall not assign, transfer, or sublet the whole or any part of the contract without the prior written approval of the Procuring Agency to subcontractor.

Any subletting or subcontracting carried out without such approval shall constitute a material violation of the Contract and shall render the Contractor liable to termination of the Contract, forfeiture of Performance Security, blacklisting, and any other action permissible under the prevailing procurement rules and laws.

BIDDER'S INFORMATION: (To be filled-in by the Bidder)

1. Name of company/Individual: _____

2. Complete Postal Address: _____

3. Tel No: _____ 4. Email address: _____

5. Fax No: _____ 6. Mobile No: _____

7. Authorized Representative's name & designation:

8. Type of Business:

- (1) Sole Proprietorship ☐ (2) Partnership ☐
- (3) Corporation (Private Ltd.) ☐ (4) Corporation (Public Ltd.) ☐

9. National Tax Number& Date of issuance: _____

10. Sales Tax Registration No. GST. _____

11. Sales Tax Registration No. BRA. _____

12. Bid Validity _____ (Please specify in no. of days)

13. Total Completion Time _____ (Date of completion)

DELIVERY SCHEDULE CONDITIONS

1. Scope of Delivery & Locations

The successful bidder shall be responsible for the execution and completion of all civil works in accordance with the approved technical specifications, and Bill of Quantities (BOQ) at the designated sites of PPHI-Balochistan as specified in the Tender Document.

2. Completion Time & Work Schedule

A) Contract Period

- a. The successful bidder shall complete execution of all civil works at the designated sites of PPHI-Balochistan within 90 (ninety) days from the date of issuance of the Work Order.
- b. Works shall be carried out strictly in accordance with the approved work schedule and construction program, unless an extension is granted in writing by PPHI-Balochistan.

B) Phased Based Execution

- a. Phased or milestone-based execution may be permitted only with prior written approval of PPHI-Balochistan.
- b. Each approved phase/milestone shall remain within the overall contract period of 90 days.

C) Execution & Progress Documentation

The bidder shall submit:

- Work Completion Certificates
- Final Completion Report duly signed by the Engineer / Authorized Representative of PPHI-Balochistan

D) Penalty for Delay

Delay beyond the stipulated 90-day period, excluding delays approved in writing or arising from force majeure, shall attract liquidated damages at the rate of 0.25% per day of the value of the uncompleted portion of works, subject to a maximum of 10% of the total contract value.

E) Force Majeure

Delays caused by events beyond the bidder's control, including natural disasters, civil disturbances, acts of government, strikes, or other force majeure circumstances, must be immediately reported in writing to PPHI-Balochistan with supporting evidence. A reasonable extension may be granted at the discretion of PPHI-Balochistan.

F) Defects, Damages & Loss

The bidder shall be fully responsible for any damage, defects, poor workmanship, or loss occurring during execution of the works. Any defective or non-compliant work shall be rectified or replaced at the bidder's cost, or the equivalent cost shall be deducted from the payable amount, as determined by PPHI-Balochistan. PPHI-Balochistan will consider the delivery of contract once 100% work completion report signed by the

representative of PPHI-Balochistan and Vendor. In Case of any damaged/Loss/Theft/destruction before 100% work completion and signing of work completion certificate will not be responsibility of PPHI-Balochistan.

3. Place & Mode of Execution

The successful bidder shall be solely responsible for the mobilization of all materials, equipment, and manpower to the designated work sites as specified in the tender documents. The bidder shall ensure safe execution, completion, and handover of the works in strict accordance with the approved technical specifications, and applicable standards.

The bidder shall also provide all required tools, plant, safety gear, and qualified technical staff necessary for proper execution of the works. All arrangements relating to site establishment, storage, handling of materials, safety, and execution logistics shall be the sole responsibility of the bidder.

4. Equipment & Site Handling Requirements

The Bidder must ensure:

- a. Availability of appropriate construction equipment, machinery, and tools required for timely and quality execution of the works.
- b. Proper storage, protection, and handling of construction materials to prevent damage, deterioration, or misuse.

5. Monitoring & Reporting

The Bidder shall:

- a. Provide regular progress updates and reports as required by PPHI-Balochistan.
- b. Immediately report any delay, accident, defect, or incident affecting the execution of works.
- c. Submit Final Completion Confirmation duly acknowledged by the Engineer / Authorized Representative of PPHI-Balochistan.

DATA-SHEET OF THE ASSIGNMENT / SCOPE OF WORK

The objective of this Data Sheet / Schedule of Requirements is to provide bidders with comprehensive and clear information to fully understand the complete scope of this Work. It ensures that all requirements of the People's Primary Healthcare Initiative (PPHI-Balochistan) related to the execution, materials, workmanship, timelines, and delivery of works are clearly defined, specified, and duly incorporated, leaving no requirement unaddressed.

It is mandatory for the bidders to meet the following given specifications. All offers meeting or exceeding the following minimum required specification shall be considered for further evaluations in accordance with the evaluation criteria.

The civil works under this tender shall be executed on a Lot-wise basis, as detailed in the Data Sheet and attached BOQs. Bidders may quote for multiple; however, separate financial bids for each Lot shall be submitted. PPHI-Balochistan reserves the right to award the contract for one or multiple Lots to a single bidder, subject to availability of funds and satisfactory evaluation.

District-wise List of Sites – PPHI-Balochistan

Lot. No	Name of site	Name of Disticts	BOQs Attached
1	BHU Killi Muchan	Pishin	Attached at Pg.no 19-26
2	BHU Therata	Pishin	Attached at Pg.no 27-33
3	BHU Killi Abdullah Jan	Pishin	Attached at Pg.no 34-42
4	BHU Mandun	Pishin	Attached at Pg.no 43-48

INSTRUCTIONS FOR PREPARING TECHNICAL BID

These Instructions are being given for strict compliance by the Bidders. **Failure to fulfill any instruction given here-under may result in dis-qualification of the Bid/s.**

Proposals shall be prepared on following lines: -

1. Sealed Envelope containing the Technical Proposal should clearly state:
 - a. **"Name of Bidder"**
 - b. **"Name of Tender"**
 - c. **"TECHNICAL PROPOSAL"**
2. The portion of Technical Proposal of this bidding document duly filled, supported with Bidder's covering Letter and the technical Bid on Bidders Letter Head be attached as the Technical Proposal.
3. Technical Proposal shall be prepared keeping in view the specifications provided in the Data Sheet and the schedule of requirements or otherwise as placed demand further during the bidding process.
4. Following information should be attached/contained in the Technical Proposal: -
 - a. Receipt of payment of **bidding Document Fee** May be in terms of **Pay Order in favor of PPHI BALOCHISTAN.**
 - b. **Completion time/Delivery time**, which means; actual execution time for the titled Work.
 - c. Documentary **evidence of fulfillment of eligibility criteria** for Bidders as required by the Peoples Primary Healthcare Initiative, Balochistan. (PPHI-Balochistan).
 - d. Documentary evidence of **fulfillment of complete schedule of requirements as per evaluation criteria** including technical, administrative and service requirements of the Peoples Primary Healthcare Initiative, Balochistan (PPHI-Balochistan)

- e. **Description of status** as Partnership / authorization from the Firm / authorized importer / distributor / manufacturer / retailer etc. (as the case may be) as required by the People's Primary Healthcare Initiative, Balochistan (PPHI-Balochistan) in the schedule of requirements.
 - f. **Defect Liability Period:** details. (As applicable) as required by the Peoples Primary Healthcare Initiative, Balochistan (PPHI-Balochistan) in the schedule of requirements as mentioned.
 - g. Every page of the **Bid must be numbered, signed & stamped** by the authorized representative.
5. Attachment of any document not demanded by the Peoples Primary Healthcare Initiative (PPHI-Balochistan) at instruction of "Instruction for preparation of Technical Bid" is strictly prohibited.

Evaluation Criteria: Selection of the successful bidder shall be based on the **Single Stage-Two Envelop Method**

The procedure shall be applied as follows: -

1. **Bidders Eligibility Assessment.** Initial evaluation of the technical proposals shall be carried-out by the **PROCUREMENT COMMITTEE**, as per the requirements of the eligibility criteria laid down under the heading of "Letter of Invitation for Bids – Eligibility Criteria for Bidders" in the following manner:

Sr. No.	Bidders Eligibility Factor	Requirement	Documents Attached	
			YES	NO
01	Legal Status & Tax Registration.	Copies of valid NTN Certificate, GST & BSTS Registration Certificate (Where applicable), and Active Taxpayer Profile, duly verifiable from FBR IRIS / official FBR and BRA website.		
02	Relevant Experience	Copies of Work Orders and Completion Certificates, clearly mentioning scope, value, and dates, duly attested by Senior Executive of the firm.		
03	Financial Capacity (For Firms)	Audited Financial Statements OR Annual Income Tax Return only showing the bidder have an average turnover of PKR 15 Million for the last 03 years (2023,2024,2025)		
04	Non-Blacklisting and disclosure of litigation cases	Declaration of Non-blacklisting and disclosure of litigation cases on Non Judicial Stamp paper by the Bidder/Individual.		
05	PEC Registration	Copy of valid PEC Registration Certificate clearly showing category, specialization, and validity.		
06	Technical Capacity	Detailed CVs of the HR/Individual along with PEC registration. 01 Civil Engineer(PEC Registered) 01 Site Supervisor.		
07	Delivery time compliance	Completion time must be clearly specified in the Technical Bid. i-e 90 Days.		
08	Agreement with all the terms & conditions	Signature & company seal on every page of the bidding document.		
09	Submission of Bidding Document Fee & Bid Security	As required by the People's Primary Healthcare Initiative (PPHI-Balochistan) in the Tender Notice.		

- i. Firm must score "YES" in all requirements of the eligibility criteria to be categorized as Eligible. "NO" to any requirement of the eligibility criteria, by any bidder shall render the Firm as Ineligible.

- ii. Subsequent upon said assessment, Bidders shall be categorized as:
 - 1. Eligible Bidders
 - 2. Ineligible Bidders

2. Return of Non-Responsive Proposals & preparation of Technical Evaluation Report. Technical Proposals not conforming to the required technical, administrative or legal requirements shall be declared as “Disqualified” and consequently shall **NOT** be accepted for any further evaluation:

- i. Their financial proposals shall be returned without being opened.
- ii. Their Bid security shall be released upon their written request.
- iii. Technical Evaluation Report, shall be prepared duly signed by all the members of the Procurement Committee, giving **REASONS** for;
 - 1. Acceptance of the Eligible Bid/s and.
 - 2. Rejection of the Ineligible Bid/s.
- iv. Technical Evaluation concludes at this stage.

3. Recommendation of Procurement Committee

After Technical Qualification, the contract will be awarded to the “Lowest Financially Evaluated bidder” with minimum quoted rates among all the Technical qualified Contractors.

Note

BID GRIEVANCES

Any bidder having a grievance relating to the technical evaluation, financial evaluation, bid responsiveness, qualification, sample assessment, or bid comparison, shall submit the grievance in writing to the Chief Executive Officer, PPHI-Balochistan, for onward submission to the Grievance Redressal Committee, within three (03) working days from the date of issuance/communication of the relevant evaluation result and, in any case, prior to the award of contract. Any grievance received after the prescribed period or after the award of contract shall not be entertained. Failure to submit a grievance within the stipulated time shall constitute a waiver of the bidder's right to challenge the procurement proceedings before the Procuring Agency.



The Head Office,
People's Primary Healthcare Initiative, Balochistan.
Admin Section
Ref No. PPHI-B/H.O-BLN/CW/2026/06
Dated: _____

Financial Proposal

People's Primary Healthcare Initiative (PPHI) - Balochistan

**TENDER DOCUMENT FOR MAJOR AND MINOR CIVIL WORKS OF BASIC
HEALTH UNITS (BHUs) OF PPHI-BALUCHISTAN – DISTRICT PISHIN, 2026**

NAME OF BIDDER: _____
(To be filled-in by the Bidder)

Address: Peoples Primary Healthcare Initiative (PPHI) Balochistan
House # 8-A, Jinnah Town Samungli Road, Quetta-Pakistan.

Phone: 081-2863620

Website: www.pphib.org

1. Name of company: _____

2. Complete Postal Address: _____

3. Tel No: _____ 4. Email address: _____

5. Fax No: _____ 6. Mobile No: _____

2. Authorized Representative's name & designation:

8. Type of Business:

(1) Sole Proprietorship ☐ (2) Partnership ☐

(3) Corporation (Private Ltd.) ☐ (4) Corporation (Public Ltd) ☐

9. National Tax Number& Date of issuance: _____

10. Sales Tax Registration No. / BRA Registration No. _____

11. GST No. _____

12. BRA No. _____

13. Bid Validity: _____ (Please specify in No. of Days)

14. Total Bid Value: _____ (In Pakistani Rupees)

INSTRUCTIONS FOR PREPARING FINANCIAL PROPOSAL

These Instructions are being given for strict compliance by the Bidders. **Failure to fulfill any instruction given here-under may result in disqualification of the Bid/s.**

Financial Proposals shall be prepared on following lines: -

1. Sealed Envelope containing the Financial Proposal should clearly state:
 - a. **"Name of Bidder"**
 - b. **"Name of Tender"**
 - c. **"Financial Proposal"**
2. The portion of Financial Proposal of this bidding document duly filled, supported with Bidder's covering Letter be attached as the Financial Proposal of the bidder.
3. Following information should be attached/contained in the financial proposal: -
 - a. Original Bid Security (If required by the Peoples Primary Health Initiative (PPHI-Balochistan).
 - b. Taxes must be included along-with the price of each item.
 - c. Financial Bid shall be prepared on the Bidders Letter Head in the BOQs format attached in tender and needs to be provide in the financial proposal.

Note: Each Bidder must mention clearly the applicable rate of BRA & GST on each item of its Bid.

4. Offer must be quoted on TCA (Total Cost of Acquisition) basis at the risk & cost of the bidder. This means:
 - i. ALL costs (including duties, taxes & other Govt. payables) incurred up-to delivery at the designated location of the Peoples Primary Health Initiative (PPHI-B).
 - ii. Complete services as required in the schedule of requirements of this bidding document.
 - iii. Cost including fixation, assembling, dismantling etc. (As & where applicable).
5. BST/GST Taxes must be included along-with the price of each item/components/service.
6. In-case of any Tax exemptions, exemption certificate from the concerned Tax Office / Regional Tax Office pertaining particularly to this case may be provided; otherwise, taxes shall be deducted as per Government Policy / Rules.
7. **Financial Evaluation.** Financial Proposals of the Responsive Technical Proposals shall be publicly opened of Technically qualified bidders in the next meeting as specified in this document under the heading of "Letter of Invitation for Bid" Financial Comparative Statement / Evaluation Report of the "Responsive Proposals" shall be prepared by the **PROCUREMENT COMMITTEE** in the following manner:

Financial Evaluation Criteria

Lot No. 01					
Sr. No	BOQ Reference	Qualified Bidder 1 (Total Price – PKR) incl. all taxes	Qualified Bidder 2 (Total Price – PKR) Incl. all taxes	Qualified Bidder 3 (Total Price – PKR) Incl. all taxes	Lowest Evaluated Bidder
1	BOQ–BHU Killi Muchan				
Lot No. 02					
Sr. No	BOQ Reference	Qualified Bidder 1 (Total Price – PKR) incl. all taxes	Qualified Bidder 2 (Total Price – PKR) Incl. all taxes	Qualified Bidder 3 (Total Price – PKR) Incl. all taxes	Lowest Evaluated Bidder
1	BOQ– BHU Therata				
Lot No. 03					
Sr. No	BOQ Reference	Qualified	Qualified	Qualified	Lowest Evaluated

		Bidder 1 (Total Price – PKR) incl. all taxes	Bidder 2 (Total Price – PKR) Incl. all taxes	Bidder 3 (Total Price – PKR) Incl. all taxes	Bidder
1	BOQ–BHU Killi Abdullah Jan				
Lot No. 04					
Sr. No	BOQ Reference	Qualified Bidder 1 (Total Price – PKR) incl. all taxes	Qualified Bidder 2 (Total Price – PKR) Incl. all taxes	Qualified Bidder 3 (Total Price – PKR) Incl. all taxes	Lowest Evaluated Bidder
1	BOQ–BHU Mandun				

Moreover;

- i. Subsequently, the prepared Financial Evaluation Report shall duly be signed by all the members of the Procurement Committee.
- ii. Comparatives of Financial will be prepared and signed by the procurement Committee in detail.
- iii. If there is any discrepancy between Unit rate and total rate, the unit rate will always govern.
- iv. If there is any discrepancy in tender documents clause and Work Order Clause, the work order Clause will always govern.
- v. If there is any discrepancy between amount in words and amount in figures, the amount in words will always govern.

5. Recommendation of Procurement Committee

- I- After Financial Evaluation (of only technically approved bidders), the contract will be awarded to the “Lowest Financially Evaluated bidder lotwise” with minimum quoted rates among all the Technical Qualified Bidders.
- II- PPHI-Balochistan reserves the right to award complete work as per mentioned as detailed in data sheet of assignment of this document or partially as this shall be subject to availability of funds.

TERMS AND CONDITIONS:

1. Tenders must be quoted in Pakistani Rupees (PKR).
2. Tax Liability:
 - i. Complete Tax liability is to be borne by the Vendor/individual as per the applicable rate of tax authority.
 - ii. Quoted prices shall be **inclusive of all applicable Taxes with maintaining of %age of BRA/ GST.**
 - iii. In-case of any Tax exemptions, exemption certificate from the concerned Tax Office / Regional Tax Office pertaining particularly to this case may be provided; otherwise, taxes shall be deducted as per Government Policy / Rules.
3. Bid Security of successful bidder/s shall be released after 30 days of completion of all deliveries as per work/supply order.
4. The bid security of successful bidders submitted by the firm shall be considered as performance security. However, if the firm/vendor opts, a separate Bid Security amounting to 2% of the total work/supply order value in lieu of total bid security or performance Security.

5. Bid Security of unsuccessful bidder/s shall be released within 10 working days from the date of award of contract to the successful bidder/s.
6. Payment release is subject to 100% work completion duly signed by the authorized officials by competent authority PPHI-Balochistan.
7. Payment:
 - i. Advance payment is not allowed.
 - ii. Finance section will release 90% payment after completion of 100% work and 10% payment will be release after completion of 90 days of work completion period.
 - iii. Payment shall be made upon successful supply of 100% of the total ordered items. Payment for 50% of the supplied quantity will be processed, while 10% shall be withheld as performance security until completion of the remaining supplies. The balance payment will be released upon 100% successful delivery of the remaining items within 20 working days subject to the submission of all required documents and verification of quality as per the specifications outlined in the tender documents and approved samples.

CURRENCY & BID VALIDITY

- **Pak Rupees & 90 Days**



PEOPLE'S PRIMARY HEALTHCARE INITIATIVE BALOCHISTAN (PPHI-B)

Summary of New Major/Minor Works BHUs, District Pishin 2026

Lot No	Name of Site	Name of District	Estimated Amount
1	BHU Killi Muchan	Pishin	4,468,004
2	BHU Therata		4,336,630
3	BHU Killi Abdullah Jan		9,568,070
4	BHU Mandun		5,964,359
Total Amount (Inclusive of: All Taxes, Labor cost & Transportation charges)			24,337,063

LOT 1**BHU Killi Muchan Repair and Renovation Work**

S.No	DESCRIPTION	Length (L)	Width (W)	Hieght (H)	QTY	UNIT	RATE	AMOUNT
1	Ground Clearance and leveling							
	Levelling and dressing the ground by cutting and filling of earth in depth upto 6 inches including consolidating. (Rough Levelling in Ordinary Soil) Sloppy Area.							
					1800	Sq.ft		
2	Excavation							
	Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)							
	New Washroom (8*6) 01 Nos	28	2.50	2	140			
					140	Cu.ft		
3	PCC (Lean Concrete)							
	Providing and laying plain hand mixed cement concrete using sand approved source and crushed aggregate having maximum size upto 1-1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.							
	New Washroom (8*6) 01 Nos	28	2.50	0.250	17.50			
					17.50	Cu.ft		
4	Brick masonry							
	Providing and laying first class solid burnt brick masonry (Brick Strength:1400psi-1700psi) including scaffolding, raking out joints and curing in foundation and substructure/Basement i/c cost of testing Above 4.5" thick brickwork upto any thickness Cement sand 1 : 4							
	New Washroom (8*6) 01 Nos	28	1.125	2	63.00			
		28	0.75	10	210.00			
					273.00	Cu.ft		
5	Plaster							
	3/4 inch (19mm) thick cement plaster 1:3 using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing.							
	New Washroom (8*6) 01 Nos	28		10	560			
					560	Sft		

6	Flooring							
	Providing and laying 1:2:4 cement concrete floor using using crushed aggrgate 3/4" (19mm) and down gauge in ground floor laid in panels including formwork, consolidation, finishing and curing. 4" (100 mm) nominal thick flooring							
	New Washroom (8*6) 01 Nos	8	6.00		48			
					48	Sft		
7	Girders & T iron							
	Fabrication of heavy steel work with angle, tees, flat iron, round iron and sheet iron for making trusses, girders, tanks etc. including cutting, drilling riveting, handling, assembling and fixing but excluding erection in position as per directions of Engineer							
	Girders (1Nos)	14	3		42			
	T iron (8Nos)	12	0.5		48			
					90	kg		
8	Roofing							
	Providing and laying first class tile roof insulation comprising single layer of tiles 12"x6"x1 1/2" grouted with cement sand mortar 1:3 laid over 2.5" thick cement concrete 1:4:8 over glass wool /roof kool sheet wrapped in polythene sheet 300 gauge (0.03mm.) over a coat of PB-4 bitumen layer at the rate of 1.65 Kg./Sq.m.							
	New Washroom (8*6) 01 Nos	8	6.00		48			
					48	Sft		
9	Roof Screeding							
	Providing and laying 1:2:4 P.C.C roof screeding using crushed stone 3/4" (19mm) including formwork, consolidation, finishing and curing 3" (75mm) nominal thick P.C.C. roof screeding							
	New Washroom (8*6) 01 Nos	8	6.00		48			
	BHU Building	45	30.00		1350			
					1398	Sft		
10	LDPE Water Tank							
	Providing and fixing LDPE overhead tank 500 gallon capacity double ply, blue/white manufactured by Marjan, Master or equivalent on top of any floor							
					1	Each		
11	Distempering							

	Distempering with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sandpapering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ at least 2.20 Liter per 10 Sq.m							
	New Washroom (8*6) 01 Nos	8	6.00	5	188			
	Existing Washroom (8*6) 01 Nos	8	6.00	5	188			
	BHU Room-1	14	12.00	10	688			
	BHU Room-2	14	12.00	10	688			
	BHU Room-3	16	14.00	10	824			
	Verandah	55	8.00	10	1620			
					4196	Sft		
12	Roof Ceiling							
	Providing and fixing Gypsum Board false ceiling of approved size and texture consisting of imported powder coated aluminum angle and tee framing (size 1" x 1") hunged by approved suspension system, including provision of extra framing for lights fittings, A/C diffusers and around columns, etc, complete in all respects as directed by the Engineer. (1/4" (6.4 mm) thick laminated gypsum board)							
	BHU Room-1	14	12.00	10	168			
	BHU Room-2	14	12.00	10	168			
	BHU Room-3	16	14.00	10	224			
					560	Sq.ft		
13	Weather Coat							
	Applying weather resistant paint coating (Three coats (@ at least 3.00 Liter per 10 Sq.m) such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris.							
	New Washroom (8*6) 01 Nos	28		11	308			
	Boundary wall	250		8	4000			
	BHU Building	160		12	1920			
					6228	Sft		
14	Tilling							

	Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing.							
	Washroom (8*6) 01 Nos new + 01 existing	8	6.00	4	320			
	BHU Room-1	14	12.00	0.5	194			
	BHU Room-2	14	12.00	0.5	194			
	BHU Room-3	16	14.00	4	464			
	Verandah	55	8.00	0.5	499			
					1671	Sft		
15	Door Installation							
	Providing and fixing 1.5" (38mm) thick pressed Teak wood, 5 Ply flushed with First class wood veneering on all faces and sides fixed over deodar wood cavited core and frame work of not less than 4" (100mm) wide strips all-round with approved brass hinges, tower bolts as required							
	Washroom 02 Nos	7	2.5		35			
	Room 03 Nos	7	3.5		73.5			
					108.5	Sft		
16	Windows Installation							
	Providing and fixing hot dipped galvanized fully glazed double leaf hung steel windows and ventilators of approved section with Z-section 1.25" (32 mm) width at each edge including using approved brass sections oxidized fitting, iron lugs, cutting holes and making good the damages to walls.							
	ventilators 02 Nos	2.5	1.5		7.5			
	Windows 04 Nos	6	4		96			
					103.5	Sft		
17	Wiring							
	Concealed/open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables							
					15	Point		
18	PPRC Pipes							

	Providing, laying, cutting, jointing, testing and disinfecting PPRC pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material							
					80	ft.		
19	Wash Basins							
	Providing and fixing approved quality fixtures Wash basin 24" (610 mm) ICL Futura make							
					2	No.		
20	Water Closet							
	Providing and fixing white English W.C with glazed earthen ware 4"(100mm) trap squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC downpipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material.							
					2	Each		
21	UPVC sewerage pipes							
	Providing and Installing uPVC pipe class b having 4"(100mm inner dia) IIL, Dadex or equivalent make registered with PSQCA in sewer lines and/or laying, cutting, jointing, testing including all specials in pipe lines in trenches.							
					60	Rft		
22	Soak Pit							
	Providing and Construction of Soak Pit having diameter 3' with depth 10' , inner filled with Brick ballast/stone ballast having RCC top , complete in all respects as per drawings and as per direction of Engineer.							
					1	No		
23	Washroom Assories set				2	each		
24	Complete Solar System (2.5 KW)							
	Inverex inverter 2.5 KW				1			
	Solar Panel (Longi A Grade 585/W)				5			
	Solar Stand Frame (14 gauge)				2			
	Cable 6mm				1			
	Phoenex Tubular Batteries TR 1800 (185 AH)				2			

	Breaker Board, DB Box and other accessories One set complete in all respect				1			
25	Tuff Tilling							
	Supply and Fixing of Concrete pavers on sand cushion of different designs having thickness of 50 mm, mechanically compressed, minimum strength of 4500 psi after laboratory testing at factory and random testing at site as and when desired by the Engineer incharge complete in all respects. (50mm thick, tuff tile Coloured)							
		100	18.00		1800	Sft		
26	Main Gate Installation							
	Providing and fixing steel grated double leaf Gate with locking arrangement, and angle iron (2" x 2" x .375") for frame, middle strip 6.4 mm (.25) thick gusset plate 75 mm x 75 mm (3" x 3") at each edge and 19 mm (.75) M.S square or round bars 5/8" or 6/8" dia at 100 mm (4) center to center including two coats of red oxide paint as per the direction of Engineer Incharge.							
		9	8.00		72	sqft		
27	Sign Board and Direction Board							
	Installation and fixation of Sign Board 10x2 , Direction Board 4x4.				1	job		
28	Underground Water Tank (UGWT)							
	Circular underground water tank Dia 6' and 10' deep, complete in all respect.				1	job		
29	Waiting Area for Patients (20'x20')							
	Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)(Shingle or gravel) (Poles nos 09)							
		2	2	2	72			
					72	Cu.ft		

	Providing and laying plain hand mixed 1:4:8 cement concrete using sand approved source and crushed aggregate having maximum size upto 1-1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.(Poles nos 09)							
		2	2	0.5	18	Cu.ft		
	Providing and laying in situ cement concrete (1;2;4 cement sand & crush) using approved coarse sand and crushed aggregate having maximum size upto 3/4" (19mm) and down gauge in foundation including formwork using wooden braces and without wall ties, (Poles nos 09)							
		2	2	0.75	27	Cu.ft		
	Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such over-laps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height							
	Pole (nos 22)	10	0.67	3	442.2			
	Dis Bars (nos 40)	10	0.67	3	804			
					1246.2	kg		
					1.2462	ton		
	Providing and fixing of 2 mm thick Flat UV Stabilized Fiber Glass Reinforced Plastic Sheet roofing upto required pitch i/c fixing J or L hooks, bolts & nuts 8 mm dia. as specified							
		20	20		400	Sft		
	Total Estimated Cost							
	8% BRA							
	Total Amount (Inclusive of: All Taxes, Labour cost & Transportation charges)							

LOT2**BHU Killi Therata Repair and Renovation Work**

S.No	DESCRIPTION	Length (L)	Width (W)	Hieght (H)	QTY	UNIT	RATE	AMOUNT
1	Excavation							
	Excavation in hard soil or soft murum in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)							
	New Washroom (8*6) 01 Nos	28	2.50	2	140			
	Boundary wall	70	2.50	2	350			
					490	Cu.ft		
2	PCC (Lean Concrete)							
	Providing and laying 1:4:8 plain machine mixed cement concrete using sand approved source and crushed aggregate having maximum size upto 1-1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.							
	New Washroom (8*6) 01 Nos	28	2.50	0.250	17.50			
	Boundary wall	70	2.50	0.250	43.75			
					61.25	Cu.ft		
4	Brick masonry							
	Providing and laying first class solid burnt brick masonry (Brick Strength:1400psi-1700psi) including scaffolding, raking out joints and curing in foundation and substructure/Basement i/c cost of testing Above 4.5" thick brickwork upto any thickness Cement sand 1 : 4							
	New Washroom (8*6) 01 Nos	28	1.125	2	63.00			
		28	0.75	10	210.00			
	Boundary wall	70	1.125	2	157.50			
		70	0.75	8	420.00			
					850.50	Cu.ft		
5	Plaster							
	3/4 inch (19mm) thick cement plaster 1:3 using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing.							
	New Washroom (8*6) 01 Nos	28		10	560			
	Boundary wall	70		8	1120			
					1680	Sft		

6	Flooring							
	Providing and laying 1:2:4 cement concrete floor using using crushed aggrgate 3/4" (19mm) and down gauge in ground floor laid in panels including formwork, consolidation, finishing and curing. 4" (100 mm) nominal thick flooring							
	New Washroom (8*6) 01 Nos	8	6.00		48			
	Existing Washroom (8*6) 01 Nos	8	6.00		48			
					96	Sft		
7	Girders & T iron							
	Fabrication of heavy steel work with angle, tees, flat iron, round iron and sheet iron for making trusses, girders, tanks etc. including cutting, drilling riveting, handling, assembling and fixing but excluding erection in position as per directions of Engineer							
	Girders (1Nos)	14	3		42			
	T iron (8Nos)	12	0.5		48			
					90	kg		
8	Roofing							
	Providing and laying first class tile roof insulation comprising single layer of tiles 12"x6"x1 1/2" grouted with cement sand mortar 1:3 laid over 2.5" thick cement concrete 1:4:8 over glass wool /roof kool sheet wrapped in polythene sheet 300 gauge (0.03mm.) over a coat of PB-4 bitumen layer at the rate of 1.65 Kg./Sq.m.							
	New Washroom (8*6) 01 Nos	8	6.00		48			
					48	Sft		
9	Roof Screeding							
	Providing and laying 1:2:4 P.C.C roof screeding using crushed stone 3/4" (19mm) including formwork, consolidation, finishing and curing 3" (75mm) nominal thick P.C.C. roof screeding							
	New Washroom (8*6) 01 Nos	8	6.00		48			
	BHU Building	45	30.00		1350			
					1398	Sft		
10	LDPE Water Tank							
	Providing and fixing LDPE overhead tank 500 gallon capacity double ply, blue/white manufactured by Marjan, Master or equivalent on top of any floor							
					1	Each		
11	Distempering							

	Distempering with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sandpapering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ at least 2.20 Liter per 10 Sq.m							
	New Washroom (8*6) 01 Nos	8	6.00	5	188			
	Existing Washroom (8*6) 01 Nos	8	6.00	5	188			
	BHU Room-1	14	12.00	10	688			
	BHU Room-2	14	12.00	10	688			
	BHU Room-3	16	14.00	10	824			
	Verandah	55	8.00	10	1620			
					4196	Sft		
12	Roof Ceiling							
	Providing and fixing Gypsum Board false ceiling of approved size and texture consisting of imported powder coated aluminum angle and tee framing (size 1" x 1") hung by approved suspension system, including provision of extra framing for lights fittings, A/C diffusers and around columns, etc, complete in all respects as directed by the Engineer. (1/4" (6.4 mm) thick laminated gypsum board)							
	BHU Room-1	14	12.00	10	168			
	BHU Room-2	14	12.00	10	168			
	BHU Room-3	16	14.00	10	224			
					560	Sq.ft		
13	Weather Coat							
	Applying weather resistant paint coating (Three coats (@ at least 3.00 Liter per 10 Sq.m) such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris.							
	New Washroom (8*6) 01 Nos	28		11	308			
	Boundary wall	70		8	1120			
	BHU Building	160		12	1920			
					3348	Sft		
14	Tilling							

	Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing.							
	Washroom (8*6) 01 Nos new + 01 existing	8	6.00	4	320			
	BHU Room-1	14	12.00	0.5	194			
	BHU Room-2	14	12.00	0.5	194			
	BHU Room-3	16	14.00	4	464			
	Verandah	55	8.00	0.5	499			
					1671	Sft		
15	Door Installation							
	Providing and fixing 1.5" (38mm) thick pressed Teak wood, 5 Ply flushed with First class wood veneering on all faces and sides fixed over deodar wood cavited core and frame work of not less than 4" (100mm) wide strips all-round with approved brass hinges, tower bolts as required							
	Washroom 02 Nos	7	2.5		35			
	Room 03 Nos	7	3.5		73.5			
					108.5	Sft		
16	Windows Installation							
	Providing and fixing hot dipped galvanized fully glazed double leaf hung steel windows and ventilators of approved section with Z-section 1.25" (32 mm) width at each edge including using approved brass sections oxidized fitting, iron lugs, cutting holes and making good the damages to walls.							
	ventilators 02 Nos	2.5	1.5		7.5			
	Windows 04 Nos	6	4		96			
					103.5	Sft		
17	Wiring							
	Concealed/open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables							
					15	Point		
18	PPRC Pipes							

	Providing, laying, cutting, jointing, testing and disinfecting PPRC pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material							
					80	ft.		
19	Wash Basins							
	Providing and fixing approved quality fixtures Wash basin 24" (610 mm) ICL Futura make							
					2	No.		
20	Water Closet							
	Providing and fixing white English W.C with glazed earthen ware 4"(100mm) trap squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC downpipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material.							
					2	Each		
21	UPVC sewerage pipes							
	Providing and Installing uPVC pipe class b having 4"(100mm inner dia) IIL, Dadex or equivalent make registered with PSQCA in sewer lines and/or laying, cutting, jointing, testing including all specials in pipe lines in trenches.							
					60	Rft		
22	Soak Pit							
	Providing and Construction of Soak Pit having diameter 3' with depth 10' , inner filled with Brick ballast/stone ballast having RCC top , complete in all respects as per drawings and as per direction of Engineer.							
					1	No		
23	Washroom Assories set				2	each		
24	Complete Solar System (2.5 KW)							
	Inverex inverter 2.5 KW				1			
	Solar Panel (Longi A Grade 585/W)				5			
	Solar Stand Frame (14 gauge)				2			
	Cable 6mm				1			
	Phoenex Tubular Batteries TR 1800 (185 AH)				2			

	Breaker Board, DB Box and other accessories One set complete in all respect				1			
25	Tuff Tilling							
	Supply and Fixing of Concrete pavers on sand cushion of different designs having thickness of 50 mm, mechanically compressed, minimum strength of 4500 psi after laboratory testing at factory and random testing at site as and when desired by the Engineer incharge complete in all respects. (50mm thick, tuff tile Coloured)							
		35	18.00		630	Sft		
26	Main Gate Installation							
	Providing and fixing steel grated double leaf Gate with locking arrangement, and angle iron (2" x 2" x .375") for frame, middle strip 6.4 mm (.25") thick gusset plate 75 mm x 75 mm (3" x 3") at each edge and 19 mm (.75") M.S square or round bars 5/8" or 6/8" dia at 100 mm (4") center to center including two coats of red oxide paint as per the direction of Engineer incharge.							
		9	8.00		72	sqft		
27	Sign Board and Direction Board							
	Installation and fixation of Sign Board 10x2 , Direction Board 4x4.				1	job		
28	Underground Water Tank (UGWT)							
	Circular underground water tank Dia 6' and 10' deep, complete in all respect.				1	job		
29	Waiting Area for Patients (20'x15')							
	Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m) (Shingle or gravel) (Poles nos 09)							
		2	2	2	72			
					72	Cu.ft		

	Providing and laying plain hand mixed 1:4:8 cement concrete using sand approved source and crushed aggregate having maximum size upto 1-1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.(Poles nos 09)							
		2	2	0.5	18	Cu.ft		
	Providing and laying in situ cement concrete (1;2;4 cement sand & crush) using approved coarse sand and crushed aggregate having maximum size upto 3/4" (19mm) and down gauge in foundation including formwork using wooden braces and without wall ties, (Poles nos 09)							
		2	2	0.75	27	Cu.ft		
	Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such over-laps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height							
	Pole (nos 22)	10	0.67	3	442.2			
	Dis Bars (nos 36)	10	0.67	3	723.6			
					1165.8	kg		
					1.1658	ton		
	Providing and fixing of 2 mm thick Flat UV Stabilized Fiber Glass Reinforced Plastic Sheet roofing upto required pitch i/c fixing J or L hooks, bolts & nuts 8 mm dia. as specified							
		20	15		300	Sft		
	Total Estimated Cost							
	8% BRA							
	Total Amount (Inclusive of: All Taxes, Labour cost & Transportation charges)							

LOT 3**BHU Killi Abdullah Jan Repair and Renovation Work**

S.No	DESCRIPTION	Length (L)	Width (W)	Hieght (H)	QTY	UNIT	RATE	AMOUNT
1	Ground Clearance and leveling							
	Levelling and dressing the ground by cutting and filling of earth in depth upto 6 inches including consolidating. (Rough Levelling in Ordinary Soil) Sloppy Area.							
		70.00	80.00		5,600.00	Sq.ft		
2	Excavation							
	Excavation in hard soil or soft murum in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)							
	BHU Building Footing 3 rooms+verandah+attach washroom nos 02	435.00	2.50	2.00	2,175.00			
	Boundary wall	304.00	2.50	2.00	1,520.00			
					3,695.00	Cu.ft		
3	PCC (Lean Concrete)							
	Providing and laying plain hand mixed cement concrete using sand approved source and crushed aggregate having maximum size upto 1-1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.							
	BHU Building Footing 3 rooms+verandah+attach washroom nos 02	435.00	2.50	0.25	271.88			
	Boundary wall	304.00	2.50	0.25	190.00			
					461.88	Cu.ft		
4	Reinforced cement concrete							
	16 nos columns for Rooms, Verandah and attach washroom 9" * 9" main bar # 4 stirups # 3 @ 6 c/c	0.75	0.75	12.00	600.17	kg		
	20 nos columns for Boundary wall 9" * 9" main bar # 4 stirups # 3 @ 6 c/c	0.75	0.75	8.00	500.15	kg		
	Door band for rooms verandah and washrooms 9" * 9" main bar # 4 stirups # 3 @ 6 c/c	220.00	0.75	0.75	550.16	kg		
	concreting							
	Room+verandah+washroom Columns	0.75	0.75	12.00	121.50			
	Boundary wall Columns	0.75	0.75	8.00	90.00			
	Door band	220.00	0.75	0.75	123.75			

					335.25	Cu.ft		
5	Brick masonry							
	Providing and laying first class solid burnt brick masonry (Brick Strength:1400psi-1700psi) including scaffolding, raking out joints and curing in foundation and substructure/Basement i/c cost of testing Above 4.5" thick brickwork upto any thickness Cement sand 1 : 4							
	BHU Building 3 rooms+verandah+attach washroom nos 02	435.00	1.13	2.00	978.75			
		435.00	0.75	10.00	3,262.50			
	Boundary wall	304.00	1.13	2.00	684.00			
		304.00	0.75	6.00	1,368.00			
					6,293.25	Cu.ft		
6	Plaster							
	3/4 inch (19mm) thick cement plaster 1:3 using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing.							
	Room-1	15.00	13.00	10.00	560.00			
	Room-2	15.00	13.00	10.00	560.00			
	Room-3	16.00	15.00	10.00	620.00			
	Verandah	16.00	8.50	10.00	490.00			
	Washroom 02nos	8.00	6.00	10.00	560.00			
	Boundary Wall	304.00		6.00	3,648.00			
					6,438.00	Sft		
7	Flooring							
	Providing and laying 1:2:4 cement concrete floor using using crushed aggregate 3/4" (19mm) and down gauge in ground floor laid in panels including formwork, consolidation, finishing and curing. 4" (100 mm) nominal thick flooring							
	Room-1	15.00	13.00	10.00	195.00			
	Room-2	15.00	13.00	10.00	195.00			
	Room-3	16.00	15.00	10.00	240.00			
	Verandah	16.00	8.50	10.00	136.00			
	Washroom 02nos	8.00	6.00	10.00	96.00			
					862.00	Sft		
8	Girders & T iron							

	Fabrication of heavy steel work with angle, tees, flat iron, round iron and sheet iron for making trusses, girders, tanks etc. including cutting, drilling riveting, handling, assembling and fixing but excluding erection in position as per directions of Engineer							
	Girders (20Nos)	14.00	3.00		840.00			
	T iron (72Nos)	12.00	0.50		432.00			
					1,272.00	kg		
9	Roofing							
	Providing and laying first class tile roof insulation comprising single layer of tiles 12"x6"x1 1/2" grouted with cement sand mortar 1:3 laid over 2.5" thick cement concrete 1:4:8 over glass wool / roof kool sheet wrapped in polythene sheet 300 gauge (0.03mm.) over a coat of PB-4 bitumen layer at the rate of 1.65 Kg./Sq.m.							
	Room-1	16.00	14.00		224.00			
	Room-2	16.00	14.00		224.00			
	Room-3	17.00	16.00		272.00			
	Verandah	16.00	8.50		136.00			
	Washroom 02nos	9.00	7.00		126.00			
					982.00	Sft		
10	Roof Screeding							
	Providing and laying 1:2:4 P.C.C roof screeding using crushed stone 3/4" (19mm) including formwork, consolidation, finishing and curing 3" (75mm) nominal thick P.C.C. roof screeding							
	Room-1	16.00	14.00		224.00			
	Room-2	16.00	14.00		224.00			
	Room-3	17.00	16.00		272.00			
	Verandah	16.00	8.50		136.00			
	Washroom 02nos	9.00	7.00		126.00			
					982.00	Sft		
11	LDPE Water Tank							
	Providing and fixing LDPE overhead tank 500 gallon capacity double ply, blue/white manufactured by Marjan, Master or equivalent on top of any floor							
					1.00	Each		
12	Distempering							

	Distempering with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sandpapering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ at least 2.20 Liter per 10 Sq.m							
	Room-1	15.00	13.00	10.00	755.00			
	Room-2	15.00	13.00	10.00	755.00			
	Room-3	16.00	15.00	10.00	860.00			
	Verandah	16.00	8.50	10.00	626.00			
	Washroom 02nos	8.00	6.00	6.00	432.00			
					3,428.00	Sft		
13	Roof Ceiling							
	Providing and fixing Gypsum Board false ceiling of approved size and texture consisting of imported powder coated aluminum angle and tee framing (size 1" x 1") hunged by approved suspension system, including provision of extra framing for lights fittings, A/C diffusers and around columns, etc, complete in all respects as directed by the Engineer. (1/4" (6.4 mm) thick laminated gypsum board)							
	Room-1	15.00	13.00	10.00	195.00			
	Room-2	15.00	13.00	10.00	195.00			
	Room-3	16.00	15.00	10.00	240.00			
	Verandah	16.00	8.50	10.00	136.00			
					766.00	Sq.ft		
14	Weather Coat							
	Applying weather resistant paint coating (Three coats (@ at least 3.00 Liter per 10 Sq.m) such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris.							
	Boundary wall	304.00		6.00	3,648.00			
	BHU Building	160.00		12.00	1,920.00			
					5,568.00	Sft		
15	Tilling							
	Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing.							

	Room-1	15.00	13.00	0.50	223.00			
	Room-2	15.00	13.00	0.50	223.00			
	Room-3	16.00	15.00	0.50	271.00			
	Verandah	16.00	8.50	0.50	160.50			
	Washroom 02nos	8.00	6.00	4.00	272.00			
					1,149.50	Sft		
16	Door Frame Installation							
	Providing and fixing moulded steel door frame of approved profile, manufactured from zinc-coated mild steel sheets 16 gauge made by Shahah Industries or equivalent standard conforming to B.S.S.1245, treated with special primer base paint all round, fitted with six fixing lugs, three steel hinges for fixing door shutters standard lock-strike plate, one sliding bolt eye, and three rubber buffers, including cutting holes and making good damages to walls and filling the door frame cavity with lean cement mortar 1:4 as directed by the Engineer Incharge.							
	Washroom 02 Nos	7.00	2.50		33			
	Room 03 Nos	7.00	3.00		51			
	Main Entrance	7.00	4.00		18			
					102.00	Rft		
17	Door Installation							
	Providing and fixing 1.5" (38mm) thick pressed Teak wood, 5 Ply flushed with First class wood veneering on all faces and sides fixed over deodar wood cavited core and frame work of not less than 4" (100mm) wide strips all-round with approved brass hinges, tower bolts as required							
	Washroom 02 Nos	7.00	2.50		35.00			
	Room 03 Nos	7.00	3.00		63.00			
	Main Entrance	7.00	4.00		28.00			
					126.00	Sft		
18	Windows Installation							
	Providing and fixing hot dipped galvanized fully glazed double leaf hung steel windows and ventilators of approved section with Z-section 1.25" (32 mm) width at each edge including using approved brass sections oxidized fitting, iron lugs, cutting holes and making good the damages to walls.							

	ventilators 02 Nos	2.50	1.50		7.50			
	Windows 04 Nos	6.00	4.00		96.00			
					103.50	Sft		
19	Wiring							
	Concealed/open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables							
					30.00	Point		
20	PPRC Pipes							
	Providing, laying, cutting, jointing, testing and disinfecting PPRC pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material							
					120.00	ft.		
21	Wash Basins							
	Providing and fixing approved quality fixtures Wash basin 24" (610 mm) ICL Futura make							
					2.00	No.		
22	Water Closet							
	Providing and fixing white English W.C with glazed earthen ware 4"(100mm) trap squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC downpipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material.							
					2.00	Each		
23	UPVC sewerage pipes							
	Providing and Installing uPVC pipe class b having 4"(100mm inner dia) IIL, Dadex or equivalent make registered with PSQCA in sewer lines and/or laying, cutting, jointing, testing including all specials in pipe lines in trenches.							
					80.00	Rft		
24	Soak Pit							

	Providing and Construction of Soak Pit having diameter 3' with depth 10' , inner filled with Brick ballast/stone ballast having RCC top , complete in all respects as per drawings and as per direction of Engineer.							
					1.00	No		
25	Washroom Assories set				2.00	each		
26	Complete Solar System (2.5 KW)							
	Inverex inverter 2.5 KW				1.00			
	Solar Panel (Longi A Grade 585/W)				5.00			
	Solar Stand Frame (14 gauge)				2.00			
	Cable 6mm				1.00			
	Phoenix Tubular Batteries TR 1800 (185 AH)				2.00			
	Breaker Board, DB Box and other accessories One set complete in all respect				1.00			
27	Tuff Tilling							
	Supply and Fixing of Concrete pavers on sand cushion of different designs having thickness of 50 mm, mechanically compressed, minimum strenght of 4500 psi after laboratory testing at factory and random testiing at site as and when desired by the Engineer inchange comple in all respects. (50mm thick,tuff tile Cloured)							
		100.00	18.00		1,800.00	Sft		
28	Main Gate Installation							
	Providing and fixing steel grated double leaf Gate with locking arrangement, and angle iron (2" x 2" x .375") for frame, middle strip 6.4 mm (.25) thick gusset plate 75 mm x 75 mm (3" x 3") at each edge and 19 mm (.75) M.S square or round bars 5/8" or 6/8" dia at 100 mm (4) center to center including two coats of red oxide paint as per the direction of Engineer Incharge.							
		9.00	8.00		72.00	sqft		
29	Sign Board and Direction Board							
	Installation and fixation of Sign Board 10x2 , Dirction Board 4x4.				1.00	job		
30	Underground Water Tank (UGWT)							
	Circular underground water tank Dia 6' and 10' deep, complete in all respect.				1.00	job		
31	Waiting Area for Paitients (20'*20')							

	Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)(Shingle or gravel) (Poles nos 09)							
		2.00	2.00	2.00	72.00			
					72.00	Cu.ft		
	Providing and laying plain hand mixed 1:4:8 cement concrete using sand approved source and crushed aggregate having maximum size upto 1-1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing. (Poles nos 09)							
		2.00	2.00	0.50	18.00	Cu.ft		
	Providing and laying in situ cement concrete (1;2;4 cement sand & crush) using approved coarse sand and crushed aggregate having maximum size upto 3/4" (19mm) and down gauge in foundation including formwork using wooden braces and without wall ties,(Poles nos 09)							
		2.00	2.00	0.75	27.00	Cu.ft		
	Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such over-laps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height							
	Pole (nos 22)	10.00	0.67	3.00	442.20			
	Dis Bars (nos 40)	10.00	0.67	3.00	804.00			
					1,246.20	kg		
					1.25	ton		

	Providing and fixing of 2 mm thick Flat UV Stabilized Fiber Glass Reinforced Plastic Sheet roofing upto required pitch i/c fixing J or L hooks, bolts & nuts 8 mm dia. as specified							
		20.00	20.00		400.00	Sft		
	Total Estimated Cost							
	8% BRA							
	Total Amount <i>(Inclusive of: All Taxes, Labour cost & Transportation charges)</i>							

LOT 4

BHU Killi Mandun Repair and Renovation Work								
S.No	DESCRIPTION	Length (L)	Width (W)	Hieght (H)	QTY	UNIT	RATE	AMOUNT
1	Ground Clearance and leveling							
	Levelling and dressing the ground by cutting and filling of earth in depth upto 6 inches including consolidating. (Rough Levelling in Ordinary Soil) Sloppy Area.							
					4500	Sq.ft		
2	Plaster							
	3/4 inch (19mm) thick cement plaster 1:3 using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing.							
	Boundary wall both inner/outer	350		7	4900			
					4900	Sft		
3	Roof Screading							
	Providing and laying 1:2:4 P.C.C roof screeding using crushed stone 3/4" (19mm) including formwork, consolidation, finishing and curing 3" (75mm) nominal thick P.C.C. roof screeding							
	BHU Building	60	35.00		2100			
					2100	Sft		
4	LDPE Water Tank							
	Providing and fixing LDPE overhead tank 500 gallon capacity double ply, blue/white manufactured by Marjan, Master or equivalent on top of any floor							
					2	Each		
5	Distempering							
	Distempering with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sandpapering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ at least 2.20 Liter per 10 Sq.m							
	Room-1	16	14.00	11	884			
	Room-2	16	14.00	11	884			

	Room-3	16	14.00	11	884			
	Room-4	16	14.00	11	884			
	Hall	18	18.00	18	1620			
	Verandah	12	8.00	11	536			
	Washrooms 4 nos	8	6.00	6	864			
					6556	Sft		
12	Roof Ceiling							
	Providing and fixing Gypsum Board false ceiling of approved size and texture consisting of imported powder coated aluminum angle and tee framing (size 1" x 1") hung by approved suspension system, including provision of extra framing for lights fittings, A/C diffusers and around columns, etc, complete in all respects as directed by the Engineer. (1/4" (6.4 mm) thick laminated gypsum board)							
	Room-1	16	14.00	11	224			
	Room-2	16	14.00	11	224			
	Room-3	16	14.00	11	224			
	Room-4	16	14.00	11	224			
					896	Sq.ft		
13	Weather Coat							
	Applying weather resistant paint coating (Three coats (@ at least 3.00 Liter per 10 Sq.m) such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris.							
	Boundary wall	350		7	4900			
	BHU Building	160		12	1920			
					6820	Sft		
14	Tilling							
	Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing.							
	Room-1	16	14.00	0.5	254			
	Room-2	16	14.00	0.5	254			
	Room-3	16	14.00	0.5	254			
	Room-4	16	14.00	4	464			
	Hall	18	18.00	0.5	360			

	Verandah	12	8.00	0	96			
	Washrooms 4 nos	8	6.00	4	640			
					2322	Sft		
15	Door Installation							
	Providing and fixing 1.5" (38mm) thick pressed Teak wood, 5 Ply flushed with First class wood veneering on all faces and sides fixed over deodar wood cavited core and frame work of not less than 4" (100mm) wide strips all-round with approved brass hinges, tower bolts as required							
	Washroom 04 Nos	7	2.5		70			
	Room 04 Nos	7	3.5		98			
	Main Entrance	7	4		28			
					196	Sft		
16	Windows Installation							
	Providing and fixing hot dipped galvanized fully glazed double leaf hung steel windows and ventilators of approved section with Z-section 1.25" (32 mm) width at each edge including using approved brass sections oxidized fitting, iron lugs, cutting holes and making good the damages to walls.							
	ventilators 04 Nos	2.5	1.5		15			
	Windows 10 Nos	6	4		240			
					255	Sft		
17	Wiring							
	Concealed/open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables							
					40	Point		
18	PPRC Pipes							
	Providing, laying, cutting, jointing, testing and disinfecting PPRC pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material							
					160	ft.		
19	Wash Basins							
	Providing and fixing approved quality fixtures Wash basin 24" (610 mm) ICL Futura make							

					4	No.		
20	Water Closet							
	Providing and fixing white English W.C with glazed earthen ware 4"(100mm) trap squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC downpipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material.							
					4	Each		
21	UPVC sewerage pipes							
	Providing and Installing uPVC pipe class b having 4"(100mm inner dia) IIL, Dadex or equivalent make registered with PSQCA in sewer lines and/or laying, cutting, jointing, testing including all specials in pipe lines in trenches.							
					160	Rft		
22	Soak Pit							
	Providing and Construction of Soak Pit having diameter 3' with depth 10' , inner filled with Brick ballast/stone ballast having RCC top , complete in all respects as per drawings and as per direction of Engineer.							
					2	No		
23	Washroom Assories set				4	each		
24	Complete Solar System (2.5 KW)							
	Inverex inverter 2.5 KW				1			
	Solar Panel (Longi A Grade 585/W)				5			
	Solar Stand Frame (14 gauge)				2			
	Cable 6mm				1			
	Phoenex Tubular Batteries TR 1800 (185 AH)				2			
	Breaker Board, DB Box and other accessories One set complete in all respect				1			
25	Tuff Tilling							

	Supply and Fixing of Concrete pavers on sand cushion of different designs having thickness of 50 mm, mechanically compressed, minimum strength of 4500 psi after laboratory testing at factory and random testing at site as and when desired by the Engineer incharge complete in all respects. (50mm thick, tuff tile Coloured)							
		100	18.00		1800	Sft		
26	Main Gate Installation							
	Providing and fixing steel grated double leaf Gate with locking arrangement, and angle iron (2" x 2" x .375") for frame, middle strip 6.4 mm (.25) thick gusset plate 75 mm x 75 mm (3" x 3") at each edge and 19 mm (.75) M.S square or round bars 5/8" or 6/8" dia at 100 mm (4) center to center including two coats of red oxide paint as per the direction of Engineer Incharge.							
		9	8.00		72	sqft		
27	Sign Board and Direction Board							
	Installation and fixation of Sign Board 10x2 , Direction Board 4x4.				1	job		
28	Underground Water Tank (UGWT)							
	Circular underground water tank Dia 6' and 10' deep, complete in all respect.				1	job		
29	Waiting Area for Patients (20'*20')							
	Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)(Shingle or gravel) (Poles nos 09)							
		2	2	2	72			
					72	Cu.ft		
	Providing and laying plain hand mixed 1:4:8 cement concrete using sand approved source and crushed aggregate having maximum size upto 1-1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.(Poles nos 09)							
		2	2	0.5	18	Cu.ft		

	Providing and laying in situ cement concrete (1;2;4 cement sand & crush) using approved coarse sand and crushed aggregate having maximum size upto 3/4" (19mm) and down gauge in foundation including formwork using wooden braces and without wall ties, (Poles nos 09)							
		2	2	0.75	27	Cu.ft		
	Providing, fabricating and laying deformed Grade 60 steel reinforcement (deformed bar) for all kinds of R.C.C work in foundation, plinth and including the cost of straightening, removal of rust, cutting, bending, binding, wastage and providing such over-laps as are not shown on the drawings. The cost of binding wire and cement concrete spacer blocks or chairs for binding and holding the reinforcement in position is inclusive upto 15 ft. (5m) height							
	Pole (nos 22)	10	0.67	3	442.2			
	Dis Bars (nos 40)	10	0.67	3	804			
					1246.2	kg		
					1.2462	ton		
	Providing and fixing of 2 mm thick Flat UV Stabilized Fiber Glass Reinforced Plastic Sheet roofing upto required pitch i/c fixing J or L hooks, bolts & nuts 8 mm dia. as specified							
		20	20		400	Sft		
	Total Estimated Cost							
	8% BRA							
	Total Amount (Inclusive of: All Taxes, Labour cost & Transportation charges)							

DECLARATION BY THE BIDDER

I solemnly undertake that:

- a. Having read, understood & made myself aware of all the Terms & conditions mentioned in this Bidding Document & the Rules, Regulations & Policies of the Government of Balochistan, governing the procurement & financial matters, **AGREE, ACCEPT & UNDETAKE TO ABIDE BY THE SAME.**
- b. The information provided in this form is correct to the best of my knowledge & in the event of change; details will be provided as soon as possible

Name & Designation _____

Signature _____ Date _____

Company Stamp. _____