



**The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.**

**No:** PPHI/ (DSU-QTA) DSM/2025/2461

**Dated:** 30<sup>th</sup> May, 2025

**Tender Notice**

**District Support Unit, PPHI-Quetta** intends to seek sealed and stamped tender from registered, firm/ contractors for Civil Work Repair & Renovation Quarter BIU Nasaran as per following details: -

S No	Detail of works	Length	Width	Height	Quantity	Estimated Cost Rs.
01	<b>Plaster:-</b> 3/4 inch (19mm) thick cement plaster 1:3 using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. Plaster patches need base+ Including entrance steps				500 Sft	=1,095,232/=
02	<b>Distempering:-</b> Distempering with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sandpapering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ at least 2.20 Liter per 10 Sq.m. <b>Room-1. Room-2, Kitchen, Washroom-1 (Shower), Washroom-2 (Toilet), Verandah</b>	55	43	66	2495 Sft	
03	<b>Weather Coat:-</b> Applying weather resistant paint coating (Three coats (@ at least 3.00 Liter per 10 Sq.m) such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris. Quarter building exterior+ boundary wall. Quarter building exterior+ boundary wall.	150		12	1800 Sft	
04	<b>Tilling:-</b> Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any color and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching	17	15	14	381 Sft	

**PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).**

19-B PPHI Office Near Passport Office Jinnah Town Quetta.

Ph.: 081-2086628

Email: dsuquetta@gmail.com



**The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.**

**No: PPHI/ (DSU-QTA) DSM/2025/\_\_\_\_\_**

	color by using color pigment and curing. <b>Washroom-1 (Shower), Washroom-2 (Toilet), Kitchen</b>				
05	<b>Kitchen Shelf with Sink:-</b>				
	Providing and erecting RCC Kitchen shelf of dimensions 6.5' x 2' x 3' with 2" thick concrete slab , with necessary partitions with at appropriate distance, one Sink at the end with double way CP MIXER with 2" flexible pipe for outside drainage, with 4" PVC pipes for drainage complete in all respect as per directions of the Engineer.				01 L
06	<b>Tuff Tilling:-</b>				
	Supply and Fixing of Concrete pavers on sand cushion of different designs having thickness of 50 mm, mechanically compressed, minimum strength of 4500 psi after laboratory testing at factory and random testing at site as and when desired by the Engineer inchange comple in all respects. (50mm thick, tuff tile Colored). Quarter External Front Yard	24	21		504 Sft
07	<b>Underground Water Tank:-</b>				
	Circular underground water tank 6'(ft) dia and 10'(ft) deep, complete in all respect.				01 Job
08	<b>Ceiling Fans:-</b>				02 Each
09	<b>Wiring:-</b>				
	Concealed/open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables				20 Point
10	<b>PPRC Pipes:-</b>				
	Providing, laying, cutting, jointing, testing and disinfecting PPRC Pipe PN20 32mm) Outer dia confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material				100 Ft
11	<b>Wash Basins:-</b>				01 No

**PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).**

19-B PPHI Office Near Passport Office Jinnah Town Quetta.

Ph.: 081-2086628

Email: dsuquetta@gmail.com





PPHI-B

The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.

No: PPHI/ (DSU-QTA) DSM/2025/\_\_\_\_\_

	Providing and fixing approved quality fixtures Wash basin 24" (610 mm) ICL Futura make.					
12	<b>Water Closet:-</b> Providing and fixing white English/indian W.C with glazed earthen ware 4"(100mm) trap squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC downpipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material.				01 Each	
13	<b>LDPE Water Tank:-</b> Providing and fixing LDPE overhead tank 500 gallon capacity double ply, blue/white manufactured by Marjan, Master or equivalent on top of any floor				01 Each	
14	<b>UPVC sewerage pipes:-</b> Providing and Installing uPVC pipe class b having 4"(100mm inner dia) ILL, Dadex or equivalent make registered with PSQCA in sewer lines and/or laying, cutting, jointing, testing including all specials in pipe lines in trenches.				20 Rft	
15	<b>Soak Pit:-</b> Providing and Construction of Soak Pit having diameter 3' with depth 20' , inner filled with Brick ballast/stone ballast having RCC top , complete in all respects as per drawings and as per direction of Engineer.				01 No	
16	<b>Water Pumping Machine:-</b> Donkey Pump 2900 RPM 2 HP				01 Each	
17	<b>Washroom Assories set:-</b>				01 Each	
18	<b>Miscellaneous works</b> (glass repair, windows mesh repair, door repair/repainting, Gate Repair/paint, minor plumbing repair etc)				01 Each	

PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).

19-B PPHI Office Near Passport Office Jinnah Town Quetta.

Ph.: 081-2086628

Email: dsuquetta@gmail.com




**The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.**

**No: PPHI/ (DSU-QTA) DSM/2025/\_\_\_\_\_**

**Terms and Conditions**

1. The firm/contractor must have **Pakistan Engineering Council Certificate** valid till **30<sup>th</sup> June, 2025**
2. The firm/Contractor must have valid NTN and BST Number.
3. Tender documents can be obtained from PPHI-DSU Quetta Office within (07 working days of publication of this advertisement i.e. **30<sup>th</sup> May, 2025** by submitting demand draft/pay order/call deposited of **Rs. 2,000/=** as tender fee (**Non-Refundable**) in favor of PPHI DSU Quetta (D.G).
4. The firm/ Contractor must have deposited 2% of the total amount as security Deposit in the form of demand draft/call deposit/pay order in favor of **PPHI-Quetta (D.G) (Refundable)**
5. The firm/contractor will submit Financial and Technical Proposal Separately in sealed and stamped envelopes.
6. All the applicable Govt Taxes will be withheld at the time of payment from the firm/contractor.
7. District Support Unit, PPHI-Quetta reserve the right to accept or cancel any tender document without any reason.
8. Last date for submission of tender Document is **05<sup>th</sup> JUNE, 2025 PPHI-DSU Quetta Office 19-B Near Passport Office Jinnah Town Quetta till 3:00PM.**
9. The Opening of Technical Bids was on **11<sup>th</sup> June, 2025 Time 11 PM.**
10. The Opening of Financial Bids was on **12<sup>th</sup> June, 2025 time 02 PM.**

  
(Farid Pancaiz)  
District Support Manager  
PPHI-DSU Quetta