



The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.

No: PPHI/ (DSU-QTA) DSM/2025/2559

Dated: 12<sup>th</sup> June, 2025

**Tender Notice**

District Support Unit, PPHI-Quetta intends to seek sealed and stamped tender from registered, firm/ contractors for Civil Work Repair & Renovation BHU New Marri Abad as per following details: -

S No	Detail of works	Length	Width	Height	Quantity	Estimated Cost Rs.
01	<b>Plaster:-</b> 3/4 inch (19mm) thick cement plaster 1:3 using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. Plaster Patching Different Areas of Building Interior and Exterior need basis				1000 Sft	=3,364,075/=
02	<b>Flooring:-</b> Providing and laying 1:2:4 cement concrete floor using using crushed aggregate 3/4" (19mm) and down gauge in ground floor laid in panels including formwork, consolidation, finishing and curing. 4" (100 mm) nominal thick flooring, Biding Side way concrete flooring	15	10		150 Sft	
03	<b>Roof Chemical treatment:-</b> Providing and laying chemical treatment on existing slabs for seepage protection. BHU Building complete				1500 Sft	
04	<b>LDPE Water Tank:-</b> Providing and fixing LDPE overhead tank 500 gallon capacity double ply, blue/white manufactured by Marjan, Master or equivalent on top of any floor.				01 Each	
05	<b>Distemping:-</b> Distemping with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sandpapering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ at least 2.20 Liter per 10 Sq.m. Room-1 (BHU Building), Room-3 (BHU Building), Room-1				6440 Sft	

PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).

19-B PPHI Office Near Passport Office Jinnah Town Quetta.

Ph.: 081-2086628

Email: dsuquetta@gmail.com



PPHI-B

The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.

No: PPHI/ (DSU-QTA) DSM/2025/ 2559

	(BHU Building), Room-4 (BHU Building), Store Room, Hall Building, Verandah (BHU Building), Washroom 04Nos.				
06	<b>Weather Coat:-</b> Applying weather resistant paint coating (Three coats (@ at least 3.00 Liter per 10 Sq.m) such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris. BHU Building exterior+ Boundary wall	210	12	2520 Sft	
07	<b>Tilling:-</b> Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing. Room-1 (BHU Building), Room-2 (BHU Building), Room-3 (BHU Building), Room-4 (BHU Building), Store Room, Hall Building, Verandah (BHU Building)			1380 Sft	
08	<b>Door Frame Installation:-</b> Providing and fixing moulded steel door frame of approved profile, manufactured from zinc-coated mild steel sheets 16 gauge made by Shahah Industries or equivalent standard conforming to B.S.S.1245, treated with special primer base paint all round, fitted with six fixing lugs, three steel hinges for fixing door shutters standard lock-strike plate, one sliding bolt eye, and three rubber buffers, including cutting holes and making good damages to walls and filling the door frame cavity with lean cement mortar 1:4 as directed by the Engineer Incharge. Rooms, Washrooms			204 Rft	
09	<b>Door Installation:-</b> Providing and fixing 1.5" (38mm) thick pressed Teak wood, 5 Ply			150.5 Sft	

PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).

19-B PPHI Office Near Passport Office Jinnah Town Quetta.

Ph.: 081-2086628

Email: dsuquetta@gmail.com





PPHI-B

The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.

No: PPHI/ (DSU-QTA) DSM/2025/ 2559

	flushed with First class wood veneering on all faces and sides fixed over deodar wood caved core and frame work of not less than 4" (100mm) wide strips all-round with approved brass hinges, tower bolts as required. 4 Rooms, 3 washrooms				
10	<b>Mesh Door Installation:-</b>				
	Providing and fixing 1.25" (32mm) thick First class deodar wood shutters partly wire gauzed with galvanized iron wire gauze 24 gauge (1.06mm) and 12 mesh to an inch (25mm) and partly panelled with deodar wood, approved S.S butt hinges and tower bolts as required. 5 Rooms	07	3.5		122.5 Sft
11	<b>Tuff Tiles:-</b>				
	Supply and Fixing of Concrete pavers on sand cushion of different designs having thickness of 50 mm. mechanically compressed. minimum strength of 4500 psi after laboratory testing at factory and random testing at site as and when desired by the Engineer incharge complete in all respects. a) 50 mm thick. tuff tiles Natural gray	25		22	1144 Sft
12	<b>PPRC Pipes:-</b>				
	Providing, laying, cutting, jointing, testing and disinfecting PPRC pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material				100 ft
13	<b>Wash Basins:-</b>				
	Providing and fixing approved quality fixtures Wash basin 24" (610 mm) ICL Futura make.				01 No -
14	<b>Water Closet:-</b>				
	Providing and fixing white English W.C with glazed earthen ware 4" (100mm) trap squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC downpipe, rubber rings/washers.				01 Each

PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).

19-B PPHI Office Near Passport Office Jinnah Town Quetta.

Ph.: 081-2086628

Email: dsuquetta@gmail.com



The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.

No: PPHI/ (DSU-QTA) DSM/2025/ 2559

	making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material.				
15	UPVC sewerage pipes:- Providing and Installing uPVC pipe class b having 4"(100mm inner dia) III. Dadex or equivalent make registered with PSQCA in sewer lines and/or laying, cutting, jointing, testing including all specials in pipe lines in trenches.			20 Rft	
16	Water Pumping Machine:- Donkey Pump 2900 RPM 2 HP			01 Each	
17	Washroom Assories (Water tank Flush)			01 Each	
18	Complete Solar System (3.5 KW)			01 Each	
19	Sign Board:- Installation and fixation of Sign Board 16x2			01 Each	
20	Installation and fixation Iron Grills:- Providing and fixing iron grills with square bars of 3/8" size as per approved design including welding all sides of the section at the junction and fixing with sunk iron screws, painting with two coats of red oxide paint and fixing in masonry/concrete or wood. window grills 03 Nos	05	05	75 Sft	
21	Miscellaneous works:- Kitchen shelf and cabenats, glass repair, windows mesh repair, Gate Repair/paint, minor plumbing repair etc			01 Job	
22	Furniture/Vase				
	Chairs			70 Each	
	Table			01 Each	
	standing desk			01 Each	
	Waiting Benches			06 Each	
	Flower Vase/Pots			12 Each	

**Terms and Conditions**

1. The firm/contractor must have **Pakistan Engineering Council Certificate** valid till **30<sup>th</sup> June, 2025**
2. The firm/Contractor must have valid NTN and BST Number.
3. Tender documents can be obtained from PPHI-DSU Quetta Office within (07 working days of publication of this advertisement i.e. **12<sup>th</sup> June, 2025** by submitting demand draft/pay order/call deposited of **Rs. 2,000/=** as tend
4. er fee (**Non-Refundable**) in favor of PPHI DSU Quetta (D.G).

PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).  
19-B PPHI Office Near Passport Office Jinnah Town Quetta.  
Ph. 081-2086628  
Email: dsuquetta@gmail.com






**The District Support Unit  
People's Primary Healthcare Initiative  
QUETTA.**

**No: PPHI/ (DSU-QTA) DSM/2025/ 2559**

5. The firm/ Contractor must have deposited 2% of the total amount as security Deposit in the form of demand draft/call deposit/pay order in favor of **PPHI-Quetta (D.G) (Refundable)**
6. The firm/contractor will submit Financial and Technical Proposal Separately in sealed and stamped envelopes.
7. All the applicable Govt Taxes will be withheld at the time of payment from the firm/contractor.
8. District Support Unit, PPHI-Quetta reserve the right to accept or cancel any tender document without any reason.
9. Last date for submission of tender Document is **18<sup>th</sup> JUNE, 2025 PPHI-DSU Quetta Office 19-B Near Passport Office Jinnah Town Quetta till 3:00PM.**
10. The Opening of Technical Bids was on **19<sup>th</sup> June, 2025 Time 11 AM.**
11. The Opening of Financial Bids was on **19<sup>th</sup> June, 2025 time 02 PM.**

  
(Farid Panzai)  
District Support Manager  
PPHI-DSU Quetta