

**The District Support Unit
People's Primary Healthcare Initiative
QUETTA.**

No: PPHI/ (DSU-QTA) DSM/2025/ 5153

Dated: 10th, September, 2025

Tender Notice

District Support Unit, PPHI-Quetta intends to seek sealed and stamped tender from registered, firm/ contractors for Civil Work Repair & Renovation BIJU Regi Nasaran as per following details: -

S No	Detail of works	Length	Width	Height	Quantity	Estimated Cost Rs.
01	Plaster:- 3/4 inch (19mm) thick cement plaster 1:3 using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. Plaster Patches (Entrance, Plinth protection, including chahja etc)	250	04		1000 Sft	=1,335,177/=
02	LDPE Water Tank:- Providing and fixing LDPE overhead tank 500 gallon capacity double ply, blue/white manufactured by Marjan, Master or equivalent on top of any floor				01 Each	
03	PPRC Pipes:- Providing, laying, cutting, jointing, testing and disinfecting PPRC Pipe PN20 25mm Outer dia confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material				100 Rft	
04	Flooring Providing and laying 1:2:4 cement concrete floor using using crushed aggregate 3/4" (19mm) and down gauge in ground floor laid in panels including formwork, consolidation, finishing and curing. 4" (100 mm) nominal thick flooring				692 Sft	
	Room-1	14	12	11		
	Room-2	14	12	11		
	Room-3	14	12	11		
	Verandah	18	06	10		
	Store	08	10	11		
05	Tilling:- Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/ Matt tiles of any colour and size in ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching	15	10	04	350 Sft	

PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).

19-B PPHI Office Near Passport Office Jinnah Town Quetta.

Ph.: 081-2086628

Email: dsuquetta@gmail.com



The District Support Unit
People's Primary Healthcare Initiative
QUETTA.

No: PPHI/ (DSU-QTA) DSM/2025/_____

	color by using color pigment and curing. Quarter 01 room for Labor Room+ wall upto 4ft				
06	Distemping:- Distemping with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sandpapering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ at least 2.20 Liter per 10 Sq.m Room-1 Room-2 Room-3 Store Washroom-1 (external) Washroom-2 (external) Verandah	14 14 14 8 6 6 18	12 12 12 10 6 6 6	11 11 11 11 11 11 11	3932 Sft
07	Weather Coat:- Applying weather resistant paint coating (Three coats (@ at least 3.00 Liter per 10 Sq.m) such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris. BHU Building exterior+ External washrooms BHU Boundry wall (both sides)	210 310		12 7	6860 Sft
08	Roof Chemical treatment:- Providing and laying chemical treatment on existing slabs for seepage protection	45	25		1125 Sft
09	Solar System Functionalization:- Solar panels fixation, Wiring need base and Solar Functionalization etc (Solar panels available already 18 nos) Stand already available				01 job
10	Miscellaneous works:- (Arch Board 12'x2', Direction Boards 4'x4', 04 nos External washrooms functionalization, Complete BHU Wiring need base, glass repair, windows mesh repair,				01 Job

PPHI-B (Regd. under Section 42 of Companies Ordinance, 1984).

19-B PPHI Office Near Passport Office Jinnah Town Quetta.

Ph.: 081-2086628

Email: dsuquetta@gmail.com




The District Support Unit
People's Primary Healthcare Initiative
QUETTA.

No: PPHI/ (DSU-QTA) DSM/2025/_____

	door repair/repainting, Gate Repair/paint, minor plumbing repair etc)						
--	---	--	--	--	--	--	--

Terms and Conditions

1. The firm/contractor must have **Pakistan Engineering Council Certificate** valid till **30th June, 2026**
2. The firm/Contractor must have valid NTN and BST Number.
3. Tender documents can be obtained from PPHI-DSU Quetta Office within (07 working days of publication of this advertisement i.e. **10th September, 2025** by submitting demand draft/pay order/call deposited of **Rs. 2,000/=** as tend
4. er fee (**Non-Refundable**) in favor of PPHI DSU Quetta (D.G).
5. The firm/ Contractor must have deposited 2% of the total amount as security Deposit in the form of demand draft/call deposit/pay order in favor of **PPHI-Quetta (D.G) (Refundable)**
6. The firm/contractor will submit Financial and Technical Proposal Separately in sealed and stamped envelopes.
7. All the applicable Govt Taxes will be withheld at the time of payment from the firm/contractor.
8. District Support Unit, PPHI-Quetta reserve the right to accept or cancel any tender document without any reason.
9. Last date for submission of tender Document is **17th September, 2025 PPHI-DSU Quetta Office 19-B Near Passport Office Jinnah Town Quetta till 3:00PM.**
10. The Opening of Technical Bids was on **18th September, 2025 Time 11:00 AM.**
11. The Opening of Financial Bids was on **18th September, 2025 time 02:00 PM.**


(Farid Panezan)
District Support Manager
PPHI-DSU Quetta