



**The District Support Unit  
People's Primary Healthcare Initiative  
Balochistan**

**(Pishin)**

**No.PPHI/(DSU-PN)ADMN/1-1/2025/3562**

**Dated: 10<sup>th</sup> October, 2025**

## **Tender Notice**

**District Support Unit, PPHI-Pishin** intends to seek sealed and stamped tender from registered firm/ contractors for Construction of Medicine Store at DSU PPHI-Pishin amounting to **Rs. 1,795,916.47/-** as per following details:


<b><u>Medicine Store Pishin</u></b>								
<b>S.No</b>	<b>DESCRIPTION</b>	<b>Length (L)</b>	<b>Width (W)</b>	<b>Hieght (H)</b>	<b>QTY</b>	<b>UNIT</b>	<b>RATE</b>	<b>AMOUNT</b>
<b>1</b>	<b>Excavation</b>							
	Excavation in hard soil or soft murum in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100 ft. (30m) & lift upto 5 ft. (1.5m)							
	Medicine Store (40*15)	110	2.00	2	440			
					440	Cu.ft		
<b>2</b>	<b>PCC (Lean Concrete)</b>							
	Providing and laying 1:4:8 plain machine mixed cement concrete using sand approved source and crushed aggregate having maximum size upto 1-1/2" (38mm) & down gauge in foundation and plinth including leveling, compacting & curing.							
	Medicine Store (40*15)	110	2.00	0.250	55.00			
					55.00	Cu.ft		
<b>3</b>	<b>Brick masonry</b>							
	Providing and laying first class solid burnt brick masonry cement sand 1 : 4 (Brick Strength: 1800psi- 2000psi) including scaffolding, raking out joints and curing in ground floor superstructure and i/c cost of testing							
	13.5" brick masonry	110	1.125	2	247.50			
					247.50	Cu.ft		
	9" brick masonry+internal partition wall	120	0.75	11	990			
					990	Cu.ft		
<b>4</b>	<b>Plaster</b>							
	Providing and applying cement plaster 1:2 using Coarse Sand with curing 1/2" (13 mm) thick							
	Medicine Store (40*15)	120		11	2640			
					2640	Sft		
<b>5</b>	<b>Flooring</b>							
	Providing and laying 1:2:4 cement concrete floor using using crushed aggregate 3/4" (19mm) and down gauge in ground floor laid in panels including formwork, consolidation, finishing and curing. 4" (100 mm) nominal thick flooring							
	Medicine Store (40*15)	40	15.00		600	Sft		

<b>6</b>	<b>Girders &amp; T iron</b>						
	Fabrication of heavy steel work with angle, tees, flat iron, round iron and sheet iron for making trusses, girders, tanks etc. including cutting, drilling riveting, handling, assembling and fixing but excluding erection in position as per directions of Engineer						
	Girders (14Nos)	14	3		588		
	T iron (55Nos)	12	0.5		330		
					918	kg	
<b>7</b>	<b>Roofing</b>						
	Providing and laying first class tile roof insulation comprising single layer of tiles 12"x6"x1 1/2" grouted with cement sand mortar 1:3 laid over 2.5" thick cement concrete 1:4:8 over glass wool / roof kool sheet wrapped in polythene sheet 300 gauge (0.03mm.) over a coat of PB-4 bitumen layer at the rate of 1.65 Kg./Sq.m.						
	Medicine Store (40*15)	40	15		600		
					600	Sft	
<b>8</b>	<b>Roof Screeding</b>						
	Providing and laying 1:2:4 P.C.C roof screeding using crushed stone 3/4" (19mm) including formwork, consolidation, finishing and curing 3" (75mm) nominal thick P.C.C. roof screeding						
	Medicine Store (40*15)	40	15		600		
					600	Sft	
<b>10</b>	<b>Distempering</b>						
	Distempering with Berger, ICI or equivalent synthetic polyvinyl emulsion finish of approved shade in two or more coats over and including the cost of priming coat including preparation of surface viz. dusting, sandpapering or rubbing with pumice stone, filling cracks or holes, if any, removing blisters or other imperfections at any height and any floor. (@ at least 2.20 Liter per 10 Sq.m						
	Medicine Store (40*15)	40	15.00	11	1810		
					1810	Sft	
<b>11</b>	<b>Weather Coat</b>						
	Applying weather resistant paint coating (Three coats (@ at least 3.00 Liter per 10 Sq.m) such as ICI/ Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sand papering and cleaning, scaffolding and removal of debris.						
	Medicine Store (40*15)	110		12	1320		
					1320	Sft	
<b>13</b>	<b>Door Installation</b>						
	Providing and fixing fully glazed steel door with frame single leaf with M.S bottom or kick rail 6" (150mm) wide and top rail of 4" (100mm) wide painted with two coats of red oxide paint, brass oxidized fittings of lugs, cutting holed, and making good the damages to walls.						
					28	Sft	
<b>14</b>	<b>Windows Installation</b>						
	Providing and fixing hot dipped galvanized fully glazed double leaf hung steel windows and ventilators of approved section with Z-section 1.25" (32 mm) width at each edge including using approved brass sections oxidized fitting, iron lugs, cutting holes and making good the damages to walls.						
	Ventilators	3	2.5		45		
					45	Sft	

15	Ceiling Fans				3	Each		
16	Wiring							
	Concealed/open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables							
					10	Point		
	<b>Total Amount</b>							
	<b>Total Amount</b> (Inclusive of: 8% BRA, Labour cost & Transportation charges)							

### **Terms and Conditions**

1. The firm/contractor must have **Pakistan Engineering Council Certificate** valid till **30<sup>th</sup> June, 2026.**
  2. The firm/Contractor must have valid NTN and BST Number.
  3. Tender documents can be obtained from PPHI-DSU Pishin Office within (10 days of publication of this advertisement i.e. **20<sup>th</sup> October, 2025** by submitting demand of **Rs. 2,000/=** as tender fee (**Non-Refundable**) in favor of PPHI-Pishin
  4. The firm/ Contractor must have submitted 2% of the total amount as security Deposit in the form of call deposit in favor of PPHI-Pishin (**Refundable**).
  5. The firm/contractor will submit Financial and Technical Proposal Separately in sealed and stamped envelopes.
  6. All the applicable Govt Taxes will be withheld at the time of payment from the firm/contractor.
  7. District Support Unit, PPHI-Pishin reserve the right to accept or cancel any tender document without any reason.
- Last date for submission of tender Documents is **20<sup>th</sup> October, 2025 at PPHI-DSU Pishin Office Cadet Collage Road Pishin Near DPO House till 12:30 PM.**

  
**(ASMATULLAH KHAN)**  
 District Support Manager  
 PPHI- DSU, Pishin