



The Head Office,
People's Primary Healthcare Initiative,
Balochistan.

Admin Section

Reference No. PPHI-B/H.O

BLN/2024/02/CW-ERC/001

Dated: _____

Technical Proposal

People's Primary Healthcare Initiative (PPHI) - Balochistan

**Bidding Document for Civil Works in Emergency Response Center
Mines Soorange Quetta and Duki Balochistan**

NAME OF BIDDER: _____
(To be filled-in by the Bidder)

Address: Peoples Primary Healthcare Initiative (PPHI) - Balochistan
House # 8-A, Jinnah Town Samungli Road, Quetta-Pakistan.

Phone: 081-2863620

Website: www.pphib.org

LETTER OF INVITATION FOR BIDS:

Sealed proposals are invited under the Peoples Primary Healthcare Initiative (PPHI-Balochistan) procurement rules, by the PPHI-B from Eligible Individuals/Firms/Constructors having expertise in Civil Works and Registered under Pakistan Engineering Council (PEC) under relevant codes:

| REQUIRED BIDDING INFORMATION | TO BE FILLED BY THE PEOPLES PRIMARY HEALTHCARE INITIATIVE (PPHI-B) |
|---|---|
| DESIGNATION OF PROCUREMENT OFFICER | MANAGER ADMIN |
| POSTAL ADDRESS OF THE PEOPLES PRIMARY HEALTH CARE INITIATIVE (PPHI-B) | PEOPLES PRIMARY HEALTHCARE INITIATIVE (PPHI-B) SAMUNGLI ROAD, QUETTA-PAKISTAN |
| PHONE NUMBER & FAX NUMBER | 081-2863620 & 081-2863623 |
| E-MAIL PPHIBLN@GMAIL.COM ADDRESS & WEBSITE | https://www.pphib.org |
| METHOD OF PROCUREMENT | SINGLE STAGE - TWO ENVELOPE BIDDING PROCEDURE |
| ISSUANCE OF BIDDING DOCUMENTS | The tender documents can be downloaded from the PPHI-B website: http://pphib.org/ |
| DEADLINE FOR SUBMISSION OF BIDS | Date: 16 April 2024 & Time Before CoB Hours directly submitted to the Head Office, PPHI-Balochistan. |
| OPENING OF TECHNICAL BIDS | Date: 16 April 2024 & Time 01:00 PM at the Head Office of PPHI-Balochistan. |
| OPENING OF FINANCIAL BIDS | Date: To be communicated after technical evaluation. |
| BIDDING DOCUMENT FEE | AMOUNT: PKR. 3,000/- PAY ORDER IN THE NAME OF PPHI Balochistan WITH TECHNICAL BID IN SEPARATE ENVELOPE |
| BID SECURITY/EARNEST MONEY | AMOUNT: 2 % OF THE QUOTED AMOUNT MANNER OF PAYMENT: <u>CALL DEPOSIT/ PAY ORDER</u> IN FAVOR OF PPHI-B BALOCHISTAN, WITH FINANCIAL BID |

ELIGIBILITY CRITERIA FOR BIDDERS:

| S. No. | Bidders Eligibility Factor | Mandatory Requirement | Document Required |
|--------|--|---|--|
| 1 | Registration with Income Tax, GST and BRA | NTN/STRN/GST Certificate AND must be on Active Tax Payer list and has active registration with BRA & Registration in relevant tariff. | Copy of <u>NTN/STRN</u> AND duly verifiable <u>Active Tax Payer Certificate</u> from FBR website & BRA. |
| 2 | Registration with Pakistan Engineering Council | Valid PEC Certificate in relevant code | Copy of Valid PEC with relevant Civil Codes should be attached. |
| 3 | Relevant Experience | Three (03) successfully completed comparable & similar assignments of Civil works (Each worth 2.5 million and above) | Copies of <u>Work Order/s</u> with relevant completion certificate/s . |
| 4 | Financial Capacity (For Firms) | Turn Over of PKR. 10 Million for the past 2 years each (2021, 2022 and 2023) (For Firms) | Audited <u>Final Accounts</u> OR Annual Tax Return Only (2021, 2022 and 2023). |
| 5 | Non-Blacklisting | Must not be presently black-listed by any Government Organization and other organization | Declaration of Non-blacklisting on <u>Non-Judicial Stamp</u> paper by the Bidder/Individual. |
| 6 | Local presence (For Firms) | The Bidder must have functional corporate/support office at Provincial level | Copy of <u>Tenancy agreement</u> or <u>ownership documents</u> of the office premises AND Copy of recently paid <u>utility Bill</u> (maximum 3 months old). |
| 7 | Technical HR | Technical HR (Engineers) with previous experience of similar assignments as required by the Peoples Primary Health Care Initiative (PPHI-B) in the Data-sheet | <u>Detailed CVs of the HR/Individual along with PEC registration.</u> |
| 8 | Delivery time compliance | Must agree to serve the Contract within agreed time i.e. 90 days | Completion time must be <u>clearly specified</u> in the Technical Bid. |
| 9 | Agreement with all the terms & conditions | Must unconditionally agree with all the instructions, terms & conditions specified in the bidding documents & contract agreement | <u>Signature & company seal on every page</u> of the bidding document. |
| 10 | Submission of Bidding Document Fee | As required by the Peoples Primary Healthcare Initiative (PPHI-B) in the Tender Notice | AMOUNT: PKR. 3,000/- Tender Fee in separate envelope with technical proposal. |

NOTE: It is mandatory for the bidders to meet all the above-mentioned requirements of eligibility. In-case of not meeting any single requirement, the Bid shall be declared NON-RESPONSIVE

BIDDER'S INFORMATION: (To be filled-in by the Bidder)

1. Name of company/Individual: _____

2. Complete Postal Address: _____

3. Tel No: _____ 4. Email address: _____

5. Fax No: _____ 6. Mobile No: _____

7. Authorized Representative's name & designation:

8. Type of Business:

- (1) Sole Proprietorship ☐ (2) Partnership ☐
(3) Corporation (Private Ltd.) ☐ (4) Corporation (Public Ltd.) ☐

9. National Tax Number & Date of issuance: _____

10. Sales Tax Registration No. / BRA Registration No. _____

11. Bid Validity _____ (Please specify in no. of days)

12. Total Completion Time _____ (Mention date of completion).

DATA-SHEET OF THE ASSIGNMENT / SCOPE OF WORK

The objective of the below given Data-Sheet / Schedule of Requirements is to provide sufficient information to bidders to understand complete scope of this procurement such that no requirement of the Peoples Primary Healthcare Initiative (PPHI-B) is left un-mentioned here under.

| S# | District | Name of Site | Nature of Work |
|-----------|-----------------|---------------------|-----------------------|
| 1 | Quetta | ERC Soorange | Civil works |
| 2 | Duki | ERC Duki | Civil works |

Note:

1. All interested Contractors/bidders are advised to visit the site before quoting rates in BOQs of Tender Documents.
2. PPHI-B reserves the right to award whole quantity of work as per BOQs or partially as this shall be subject to availability of funds & donor approval.
3. PPHI-B reserves the right to award contract of each site to separate vendors.

Delivery Schedule & Requirements:

Place of Execution of Works is: District Duki and Soorage District Quetta

INSTRUCTIONS FOR PREPARING TECHNICAL BID

These Instructions are being given for strict compliance by the Bidders. **Failure to fulfill any instruction given here-under may result in dis-qualification of the Bid/s.**

Proposals shall be prepared on following lines: -

1. Sealed Envelope containing the Technical Proposal should clearly state:
 - a. **"Name of Bidder"**
 - b. **"Name of Tender"**
 - c. **"TECHNICAL PROPOSAL"**
2. The portion of Technical Proposal of this bidding document duly filled, supported with Bidder's covering Letter and the technical Bid on Bidders Letter Head be attached as the Technical Proposal.
3. Technical Proposal shall be prepared keeping in view the specifications provided in the Data Sheet and the schedule of requirements or otherwise as placed demand further during the bidding process.
4. Following information should be attached/contained in the Technical Proposal: -
 - a. Receipt of payment of **bidding Document Fee** **May be** in terms of **Pay Order in favor of PPHI BALOCHISTAN**
 - b. **Completion time**, which means; actual execution time for the titled Work.
 - c. Documentary **evidence of fulfillment of eligibility criteria** for Bidders as required by the Peoples Primary Healthcare Initiative, Balochistan. (PPHI-B).
 - d. Documentary evidence of **fulfillment of complete schedule of requirements as per evaluation criteria** including technical, administrative and service requirements of the Peoples Primary Healthcare Initiative, Balochistan (PPHI-B)
 - e. **Description of status** as Partnership / authorization from the Firm / authorized importer / distributor / manufacturer / retailer etc. (as the case may be) as required by the Peoples Primary Healthcare Initiative, Balochistan (PPHI-B) in the schedule of requirements.
 - f. **Defect Liability Period:** details. (As applicable) as required by the Peoples Primary Healthcare Initiative, Balochistan (PPHI-B) in the schedule of requirements as mentioned.
 - g. Every page of the **Bid must be numbered, signed & stamped** by the authorized representative.
5. Attachment of any document not demanded by the Peoples Primary Healthcare Initiative (PPHI-B) at instruction 4 of "Instruction for preparation of Technical Bid" is strictly prohibited.

Evaluation Criteria: Selection of the successful bidder shall be based on the **Single Stage-Two Envelop Method**

The procedure shall be applied as follows: -

1. **Bidders Eligibility Assessment.** Initial evaluation of the technical proposals shall be carried-out by the **PROCUREMENT COMMITTEE**, as per the requirements of the eligibility criteria laid down under the heading of “Letter of Invitation for Bids – Eligibility Criteria for Bidders” in the following manner:

| Bidders Eligibility Factor | Requirement | Bidder 1 | Bidder 2 | Bidder 3 |
|--|---|----------|----------|----------|
| | | YES / NO | YES / NO | YES / NO |
| Registration with Income Tax (For Firms),BRA (if applicable) | I. Copy of NTN attached? II. BRA Certificate Copy? III. Active Tax Payer? IV. Registered with FBR & BRA in relevant tariff code? | | | |
| Registration with PEC | Copy of Valid PEC Certificate at time of Technical Bid, with Relevant code | | | |
| Relevant Experience | Three (03) No. of Work Orders with relevant completion certificate of successfully completed similar assignments attached (each worth 2.5 million or above)? | | | |
| Financial Capacity (For Firms) | Annual Audit Financial Statement OR Annual Tax Returns to Clarify the Minimum turnover of PKR. 10 million for the past 2 years each (2022 and 2023) attached? | | | |
| Agreement with all the terms & conditions | Signature & company seal at every page of bidding document affixed? | | | |
| Delivery time | Is the quoted completion time within the stipulated time period? | | | |
| Technical HR | Detailed CVs of the HR/Individual along with PEC registration? | | | |
| Non Blacklisting | Declaration of non-blacklisting by any govt, semi-govt or private organization, on judicial stamp paper attached? | | | |
| Local Presence | Copy of tenancy agreement or ownership documents and last three months paid utility bills attached? | | | |

| | | | | |
|-----------------------|--|--|--|--|
| Bidding Documents Fee | Pay order of Rs. 2,000/- in favor of PPHI-B as bidding document fees attached? | | | |
|-----------------------|--|--|--|--|

- i. Firm must score “YES” in all requirements of the eligibility criteria to be categorized as Eligible. “NO” to any requirement of the eligibility criteria, by any bidder shall render the Firm as Ineligible.
 - ii. Subsequent upon said assessment, Bidders shall be categorized as:
 1. Eligible Bidders
 2. Ineligible Bidders
2. **Return of Financial Proposals from Ineligible Bidders.** Proposals from Ineligible Bidders shall be declared “Non-Responsive”, consequently shall **NOT** be accepted for any further evaluation:
 - i. Their Financial Proposals shall be returned without being opened.
 - ii. Their Bid security shall be released upon their written request.
3. **Return of Non-Responsive Proposals & preparation of Technical Evaluation Report.** Technical Proposals not conforming to the required technical, administrative or legal requirements shall be declared as “Non-Responsive” and consequently shall **NOT** be accepted for any further evaluation:
 - i. Their financial proposals shall be returned without being opened.
 - ii. Their Bid security shall be released upon their written request.
 - iii. Technical Evaluation Report shall be prepared duly signed by all the members of the Procurement Committee, giving **REASONS** for;
 1. Acceptance of the Eligible & Responsive Bid/s and.
 2. Rejection of the Ineligible &/OR Non-Responsive Bid/s.
 - iv. Technical Evaluation concludes at this stage.
4. **Financial Evaluation.** Financial Proposals of the Responsive Technical Proposals shall be publicly opened in the next meeting as specified in this document under the heading of “Letter of Invitation for Bid” Financial Comparative Statement / Evaluation Report of the “Responsive Proposals” shall be prepared by the **PROCUREMENT COMMITTEE** in the following manner:

| <u>FINANCIAL EVALUATION OF BIDS</u> | | | | | | | |
|--|----------|---------------------|-------------|---------------------|-------------|---------------------|-------------|
| Item/s Name / Model & description | Quantity | Responsive Bidder 1 | | Responsive Bidder 2 | | Responsive Bidder 3 | |
| | | Unit Price | Total Price | Unit Price | Total Price | Unit Price | Total Price |
| Service 1 | | | | | | | |
| Service 2 | | | | | | | |
| Service 3 | | | | | | | |

- i. Subsequently, the prepared Financial Evaluation Report shall duly be signed by all the members of the Procurement Committee.
- ii. Comparatives of Financial will be prepared and signed by the procurement Committee in detail
- iii. If there is any discrepancy between Unit rate and total rate, the unit rate will always govern
- iv. If there is any discrepancy in tender documents clause and Work Order Clause, the work order Clause will always govern.
- v. If there is any discrepancy between amount in words and amount in figures, the amount in words will always govern

5. **Recommendation of Procurement Committee**

After Technical Qualification, the contract will be awarded to the “Lowest Financially Evaluated bidder” with minimum quoted rates among all the Technical qualified Contractors.



The Head Office,
People's Primary Healthcare Initiative,
Balochistan.
Admin Section
Reference No. PPHI-B/H.O
BLN/2024/02/CW-ERC/001
Dated: _____

Financial Proposal

People's Primary Healthcare Initiative (PPHI)-Balochistan

**Bidding Document for Civil Works in Emergency Response Center
Mines Soorange Quelta and Duki Balochistan**

NAME OF BIDDER: _____
(To be filled-in by the Bidder)

Address: Peoples Primary Healthcare Initiative (PPHI) Balochistan House
8-A, Jinnah Town Samungli Road, Quetta-Pakistan.

Phone: 081-2863620

Website: www.pphib.org

1. Name of company: _____

2. Complete Postal Address: _____

3. Tel No: _____ 4. Email address: _____

5. Fax No: _____ 6. Mobile No: _____

6. Authorized Representative's name & designation:

8. Type of Business:

- (1) Sole Proprietorship ☐ (2) Partnership ☐
(3) Corporation (Private Ltd.) ☐ (4) Corporation (Public Ltd) ☐

9. National Tax Number& Date of issuance: _____

10. Sales Tax Registration No. / BRA Registration No. _____

11. BTSN No. _____

12. Bid Validity: _____ (Please specify in No. of Days)

13. Total Bid Value: _____ (In Pakistani Rupees)

INSTRUCTIONS FOR PREPARING FINANCIAL PROPOSAL

These Instructions are being given for strict compliance by the Bidders. **Failure to fulfill any instruction given here-under may result in disqualification of the Bid/s.**

Financial Proposals shall be prepared on following lines: -

1. Sealed Envelope containing the Financial Proposal should clearly state:
 - a. **"Name of Bidder"**
 - b. **"Name of Tender"**
 - c. **"Financial Proposal"**
2. The portion of Financial Proposal of this bidding document duly filled, supported with Bidder's covering Letter be attached as the Financial Proposal of the bidder
3. Following information should be attached/contained in the financial proposal: -
 - a. Original Bid Security (If required by the Peoples Primary Health Initiative (PPHI-B))
 - b. Taxes must be included along-with the price of each item
 - c. Financial Bid shall be prepared on the Bidders Letter Head in the following format:

| A | B | C | D | E | | F |
|--------|-----------|----------|------------|------------|----------|----------------------------------|
| S. No. | Item Name | Quantity | Unit Price | BRA Amount | BRA %age | Total Price (Including Taxes) |
| A | B | C | D | | | (C x D) + E = F |
| 1 | | | | | | |
| 2 | | | | | | |
| 3 | | | | | | |
| 4 | | | | | | |
| Total | | | | | | |

Note: Each Bidder must mention clearly the rate of BRA & GST applicable on each item of its Bid.

4. Offer must be quoted on TCA (Total Cost of Acquisition) basis at the risk & cost of the bidder. This means:
 - i. ALL costs (including duties, taxes & other Govt. payables) incurred up-to delivery at the designated location of the Peoples Primary Health Initiative (PPHI-B).
 - ii. Complete services as required in the schedule of requirements of this bidding document.
 - iii. Cost including fixation, assembling, dismantling etc. (As & where applicable).
5. BST/GST Taxes must be included along-with the price of each item/components/service.
6. In-case of any Tax exemptions, exemption certificate from the concerned Tax Office / Regional Tax Office pertaining particularly to this case may be provided; otherwise, taxes shall be deducted as per Government Policy / Rules.
7. Every page of the Bid must be numbered, signed & stamped by the bidder.

TERMS AND CONDITIONS:

1. Completion time may be clearly specified. Where completion time shall mean; time consumed execution of required services to the designated location of Peoples Primary Health Initiative (PPHI-B), including but not limited to time required for development of Performa/forms and training (if needed) **(Complete delivery as per the schedule of requirements services detailed in the Data-Sheet)**
2. Maximum completion time for the assignment is **90 days** from the date of work Order
3. Tenders must be quoted in Pakistani Rupees (PKR).
4. Tax Liability:
 - i. Complete Tax liability is to be borne by the Vendor/individual as per the applicable rate of tax authority.
 - ii. Quoted prices shall be **inclusive of all applicable Taxes with maintaining of %age of BRA/GST. (Please note that BRA will be applicable @6%).**
 - iii. In-case of any Tax exemptions, exemption certificate from the concerned Tax Office / Regional Tax Office pertaining particularly to this case may be provided; otherwise, taxes shall be deducted as per Government Policy / Rules.
 - iv. All tax variations by the Tax Authorities will be borne by the vendor only, there will be no change in contract.
5. Validity of the bid would be 90 days (to be specified by the Peoples Primary Health Initiative (PPHI-B)/ office) from the date of Tender opening.
6. Financial Bids must be accompanied with Bid Security (for firms) in the form of Call deposit @ 2% of quoted bid value favoring the PPHI Balochistan.
7. In case of late execution of required works, the bidder may be blacklisted and late delivery penalty (Liquidated Damages) shall be imposed at the rate of 0.1% per day (of the value of items delivered late) per day, up to a maximum of 30% of the Contract Value.
8. The services, as per the work Order, must be executed by the authorized HR (technical) at the time of execution of work at both sites.
9. Bid Security of successful bidder/s shall be released upon submission of Performance Security, Otherwise Bid Security/CDR may be retained until 30% completion of work
10. Bid Security of unsuccessful bidder/s shall be released within thirty days from the date of award of contract to the successful bidder/s.
11. Tender will be awarded to the lowest quoted bidder in financial evaluation.
12. PPHI-B or its any sub office will not be responsible of any loss or theft at any site, Until completion of 100% of work completion. The concerned vendor will be responsible for any loss/damage of work at site or material at site.
13. Payment release is subject to satisfactory sign off by the joint team report and MBs comprising of:
 - i. Concerned DSM and Engineer PPHI-B.
 - ii. One member duly authorized by vendors.
14. Payment:
 - i. 40% payment will be released subject to completion report of 50% work.
 - ii. 90% payment will be released subject to completion report of 100% work.

- iii. Remaining 10% shall be withheld as performance security for the period of 90 days after completion of 100% work with satisfactory report by the above mentioned committee and donor approval.

CURRENCY & BID VALIDITY

- Pak Rupees & 90 days.

Bill of Quantities

| RECONSTRUCTION DEMOLISHING & RENOVATION WORK OF ERC SOORANGE DISTRICT QUETTA | | |
|---|---|---------------|
| S# | Description | Amount |
| 1 | Renovation of 1 No's room (L=16, W=10, H=10) 1. Scrapping of existing paint 2. Application of New paint of all room wall & ceiling 3. 2 Phillips light, 1 tube light | |
| 2 | Renovation of 1 No's Room (L=20, W=17, H=10) 1. Scrapping of existing paint 2. Application of New paint of all room wall & ceiling 3. 2 Phillips light, 1 tube light 4. Demolishing / Construction New Slab (20x26) | |
| 3 | Renovation of 1 No's Room (L=18, W=16, H=10) 1. Scrapping of existing paint 2. Application of New paint of all room wall & ceiling 3. 2 Phillips light, 1 tube light | |
| 4 | Renovation of 1 No's Room (L=13, W=10, H=10) 1. Scrapping of existing paint 2. Application of New paint of all room wall & ceiling | |
| 5 | Renovation of 1 No's Room (L=15, W=16, H=10) 1. Scrapping of existing paint 2. Application of New paint of all room wall & ceiling | |
| 6 | ENTERANCE (L=26, W=22, H=10) CORRIDOR (L=150, W=8, H=10) 1. Scrapping of existing paint 2. Application of New paint of all room wall & ceiling | |

| | | |
|--|--|--|
| 7 | Renovation of Bath Room (L=8 , W=6, H=10) Floor & Wall Tiles Paint Work Light Point Bath Set | |
| 8 | Construction of New Washroom Internal Area (L= 8, W=7, H=10) Complete With All respect | |
| 9 | Paint Work of Main Gate (12x9) | |
| 10 | Parking Shade (42 x 13) Steel Frame with fiber | |
| 11 | Screeding/Chipsing (2inch) whole roof slab Total Area = 7500 Sft. | |
| 12 | Providing Ramp at main entrance (18x15) height 5ft, along with marble on steps and single side hand railing | |
| Total Amount (Inclusive of All Taxes) | | |

**EMERGENCY RESPONSE CENTER
DUKI ERC**

CIVIL WORK

| S# | DESCRIPTION | QUANTITY | UNIT | RATE /UNIT | AMOUNT |
|---------------------|--|-----------------|-------------|-------------------|---------------|
| DEMOLISHING | | | | | |
| 1 | Dismantling cement block masonry upto 8" width | | | | |
| | | 88.44 | | | |
| | | 36.67 | | | |
| | | 125.11 | CFT | | |
| CONSTRUCTION | | | | | |
| 2 | Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4" (19mm) and down gauge in slabs including formwork and its removal, compacting and curing | | | | |
| | Kitchen Shelf Slab | 8.00 | | | |
| | | 3.96 | | | |
| | Total Quantity | 11.96 | CFT | | |
| 3 | Providing and laying (1:3:6) cement concrete block masonry using Coarse Sand and Approved crushed aggregate 3/4" (19mm) and down gauge in ground floor super-structure including scaffolding, raking out joints and curing. Cement sand mortar 1 : 4 | | | | |
| | Existing gate | 16.75 | CFT | | |
| | Existing Windows | 58.96 | CFT | | |
| | Exist B-Wall up to 5' | 211.05 | CFT | | |
| | Kitchen Shelf | 10.67 | CFT | | |
| | TOTAL | 297.43 | CFT | | |
| 3 | Providing and laying (1:3:6) cement concrete block masonry using Coarse Sand and Approved crushed aggregate 3/4" (19mm) and down gauge in ground floor super-structure including scaffolding, raking out joints and curing. Cement sand mortar 1 : 4 | | | | |
| | Partition Wall | 132.00 | CFT | | |
| 4 | 1/2 inch (13mm) thick cement plaster using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. | | | | |

| | | | | | |
|----------|---|-------|------------|--|--|
| | Existing gate | 50 | | | |
| | Existing Windows | 176 | | | |
| | Exist B-Wall up to 5' | 630 | | | |
| | Partition Wall | 792 | | | |
| | | 1648 | SFT | | |
| 5 | Providing and fixing 1/4" to 3/8" (6mm to 9mm) thick Ceramic Glazed/Matt tiles (Prime Quality) of any colour and size, as directed by Engineer-in-Charge in dado/skirting on ground floor over 1/2" (13mm) thick base of cement mortar 1:3, setting of tiles in slurry of grey cement over mortar base including filling the joints and washing the tiles with white cement slurry of matching color, cleaning & curing | | | | |
| | Room Type-1 (15x18) | 1080 | | | |
| | Bath Room (8x6) | 144 | | | |
| | Kitchen (8x12) | 96 | | | |
| | TOTAL | 1320 | SFT | | |
| 6 | Providing and laying 3/4" (19mm) thick mosaic tiles 6"x6" sized in dado/skirting of approved design in any color, shade and pattern on ground floor over 3/8" thick base cement sand mortar 1:3 including setting the tiles with portland cement slurry over cement sand jointing and washing the tiles with cement slurry of matching color including grinding, rubbing, polishing & mortar cost. (Skirting) | | | | |
| | Room Type-1 (15x18) | 132 | | | |
| | Kitchen (8x12) | 16 | | | |
| | Total | 148 | SFT | | |
| 7 | Providing and laying 1/4" to 3/8" (6mm to 9mm) thick Glazed/Matt tiles of any colour and size on ground floor laid over 1" (25mm) thick cement sand mortar base including jointing and washing the tiles with white cement slurry of matching color by using color pigment and curing. | | | | |
| | Bath Room (8x6) Walls | 336 | | | |
| | | 252 | | | |
| | | 588 | | | |
| | D/d od Doors | 52.5 | | | |
| | Net Qty | 535.5 | SFT | | |
| | | | | | |

| | | | | | |
|---|--|-----------------|------------|--|--|
| 8 | Distempering with Berger/ICI or equivalents synthetic vinyl emulsion paint of approved shade on old surface of walls and ceiling including dusting, sandpapering and cleaning in basement and ground floor. | | | | |
| | Room Type-1(15x18) Short Wall | 1320 | | | |
| | Room Type-1(15x18) Long Wall | 1584 | | | |
| | Roof Ceiling | 1080 | | | |
| | Kitchen Shelf Sides | 64 | | | |
| | Kitchen Shelf Sides | 96 | | | |
| | Kitchen Full Size Wall | 88 | | | |
| | Kitchen Full Size Wall | 132 | | | |
| | Kitchen Roof Ceiling | 96 | | | |
| | Store (8x12) | 176 | | | |
| | | 264 | | | |
| | Store Roof Ceiling | 96 | | | |
| | Bath Room (8x6) Long Side | 240 | | | |
| | Bath Room (8x6) Short Side | 180 | | | |
| | Varendah wall | 489.5 | | | |
| | Varendah Roof | 534 | | | |
| | Store & Bath Out side front Wall | 214.5 | | | |
| | Store & Bath Out side Back Wall | 95.33 | | | |
| | Kitchen & Bath Out Front side Wall | 176 | | | |
| | Kitchen & Bath Out Back side Wall | 95.33 | | | |
| | Boundary Wall Long | 1,386.00 | | | |
| | Boundary Wall Short | 407.00 | | | |
| | Total Quantity | 8,813.67 | | | |
| | D/d of Doors & Windows | | | | |
| | W1 | 176 | | | |
| | W2 | 40 | | | |
| | D1 | 196 | | | |
| | D2 | 175 | | | |
| | Total Deduction | 587.00 | | | |
| | Net Quantity | 8,226.67 | SFT | | |
| 9 | Painting with ICI/Berger or equivalent super gloss synthetic enamel paint in two more coats as per manufacturer's instructions on wood work over and including the cost of priming coat, surface preparation, rubbing down smooth, knotted, filling cracks, holes and joints in ground floor or basement. (@at least 1.65 Litre per 10 Sq.m) | | | | |
| | Room Type-1(15x18) Short Wall | 1320 | | | |

| | | | | | |
|----|--|-----------------|------------|--|--|
| | Room Type-1(15x18) Long Wall | 1584 | | | |
| | Roof Ceiling | 1080 | | | |
| | Kitchen Shelf Sides | 64 | | | |
| | Kitchen Shelf Sides | 96 | | | |
| | Kichen Full Size Wall | 88 | | | |
| | Kichen Full Size Wall | 132 | | | |
| | Kitchen Roof Ceiling | 96 | | | |
| | Store (8x12) | 176 | | | |
| | | 264 | | | |
| | Store Roof Ceiling | 96 | | | |
| | Bath Room (8x6) Long Side | 240 | | | |
| | Bath Room (8x6) Short Side | 180 | | | |
| | Total Quantity | 5,416.00 | | | |
| | D/d of Doors & Windows | | | | |
| | W1 | 176 | | | |
| | W2 | 40 | | | |
| | D1 | 196 | | | |
| | D2 | 87.5 | | | |
| | Total Deduction | 499.50 | | | |
| | Net Quantity | 4,916.50 | SFT | | |
| | | | | | |
| 10 | Applying weather resistant paint coatings such asICI/Berger or equivalent paint of approved shade on old surface of walls and ceiling including dusting, sandpapering and cleaning, scaffolding and removal of debris. | | | | |
| | Store & Bath Out side front Wall | 214.5 | | | |
| | Store & Bath Out side Back Wall | 95.33 | | | |
| | Kitchen & Bath Out Front side Wall | 176 | | | |
| | Kitchen & Bath Out Back side Wall | 95.33 | | | |
| | Boundary Wall Long | 1,386.00 | | | |
| | Boundary Wall Short | 407.00 | | | |
| | Total Quantity | 2,374.17 | SFT | | |

| | | | | | |
|----|---|-------|------------|--|--|
| 11 | Providing and fixing moulded steel door frame of approved profile, manufactured from zinc-coated mild steel sheets 16 gauge made by Shaha Industries or equivalent standard conforming to B.S.S. 1245, treated with special primer base paint all round, fitted with six fixing lugs, three steel hinges for fixing door shutters standard lock-strike plate, one sliding holteye, and three rubber buffers, including cutting holes and making good damages to walls and filling the door frame cavity with lean cement mortar 1:4 as directed by the Engineer Incharge. | | | | |
| | D1 (3.5+3.5+7+7) | 84 | | | |
| | D2 (2.5+2.5+7+7) | 95 | | | |
| | Total Quantity | 179 | RFT | | |
| 12 | Providing and fixing 1.5" (38mm) thick pressed veneered door shutters fully flushed with Fir class wood veneering on all faces and sides fixed over partial wood cavited core and frame work of not less than 4" (100mm) wide strips all round with approved iron hinges, tower bolts as required. | | | | |
| | D1 | 98 | | | |
| | D2 | 87.5 | | | |
| | Kitchen Shelf | 30 | | | |
| | Total Quantity | 215.5 | SFT | | |
| 13 | Providing and fixing locks with brass or specially supplied screws including Door Closers and Floor Hinges of approved design including cutting wood to required shape and size with two operating keys. | | | | |
| | Hyundi lock | | | | |
| 14 | Providing and laying 1" (25mm) thick super white marble slab exceeding 12"x12" size kitchen top in white cement including all labour for grinding and polishing | | | | |
| | Kitchen Shelf | 24 | | | |
| | | 12 | | | |
| | Total Quantity | 36 | SFT | | |

| | | | | | |
|--|---|------|-----|--|--|
| 15 | Providing and fixing hot dipped galvanized fully glazed double leaf hung steel windows and ventilators of approved section with Z-section 1.25" (32mm) width at each edge including using approved brass section oxidized fitting, iron lugs, cutting holes and making good the damages to walls. | | | | |
| | W1 | 132 | | | |
| | W2 | 20 | | | |
| | V1 | 12 | | | |
| | | 164 | SFT | | |
| 16 | Providing and fixing steel grated double leaf door with locking arrangement, angle iron 2"x2"x3/8" frame, middle strip, 1/4" thick gusset plate 3"x3" at each edge and 3/4" M.S. square or round bars at 4" c/c including two coats of red oxide paint | | | | |
| | | 28 | | | |
| | | 72 | | | |
| | | 100 | SFT | | |
| | | | | | |
| PARKING SHADE | | | | | |
| 17 | Providing and fixing Fibre Glass Window Shades 3 ft wide using 2.0 mm Decorative fibre Glass with 1"x1" 16 gauges sq. as approved by Engineer in charge including iron lugs, cutting holes and making good the damages to walls. | | | | |
| 18 | Providing and installing M.S. blind pipe socketed seamless welded joint or hand welded joint, M.S. reducer where necessary in tube well bore hole including jointing and welding with strainer of the nominal inner diameter. | | | | |
| | 4" (100 mm) dia. and (3 mm) wall thickness | 30 | Rft | | |
| 19 | Providing and installation of tuff tile | 1400 | SFT | | |
| Total Amount (Inclusive of All Taxes) | | | | | |

**EMERGENCY RESPONSE CENTER
DUKI ERC**

ELECTRICAL WORKS

| S. No | DESCRIPTION OF ITEMS | QUANTITY | UNIT | RATE (RS) | AMOUNT (RS) |
|-------|--|----------|-------|-----------|-------------|
| 1 | Concealed / open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables, (Concealed wiring with 3/4" 20 (mm) dia. PVC conduit and accessories such as bends, elbows, junction boxes etc.) | | | | |
| | Room (4x4)+(2x3)+3)+4 | 32 | Point | | |
| 2 | Concealed/open wiring for 5 Amp. Socket outlets from nearest available circuit with a length upto 20 ft. (6m) with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables. (Concealed wiring with 3/4" -20 mm) dia. PVC conduit and accessories such as bends, elbows, junction boxes etc) | | | | |
| | | 6 | Point | | |
| 3 | Provide,install,testandcommissionrecessedwallmountingtypedistributionboardfabricatedfrom16SW Gsteelsheet,powdercoatedwith approved color 2'x2'x1.5' | | | | |
| | | 1 | Each | | |
| 4 | Supply ,Installing ,Connection of 2 Pole Circuit Breaker 50 Ampere | | | | |
| | | 5 | Each | | |
| 5 | Single Pole Circuit Breaker 16 Ampere | | | | |
| 6 | Supply and install Energy Saver electric bulbs | | | | |
| | | 25 | No's | | |
| 7 | Supply and install 40W electric tube light rod including patty | | | | |
| | | 7 | No's | | |
| 8 | Supply and install 10" (250 mm) sweep exhaust fan including plastic louvers. | | | | |

| | | | | | |
|--|--|---|------|--|--|
| | | 1 | No's | | |
| 9 | Supply and install 56" (1.42m) sweep ceiling fan with fan hook and dimmer complete with all accessories. | | | | |
| | | 6 | No's | | |
| Total Amount (Inclusive of All Taxes) | | | | | |

EMERGENCY RESPONSE CENTER

DUKI ERC

PLUMBING WORKS

| S. No | DESCRIPTION OF ITEMS | QUANTITY | UNIT | RATE (RS) | AMOUNT (RS) |
|-------|---|----------|------|-----------|-------------|
| 1 | Providing and Installing uPVC blind pipe of approved make registered with PSQCA in tubewell bore hole and/or laying, cutting, jointing, testing and disinfecting uPVC pipe lines in trenches. (3" (75 mm) inner dia) | | | | |
| | GROUND FLOOR | 60 | RFT | | |
| 2 | Providing and Installing uPVC blind pipe of approved make registered with PSQCA in tubewell bore hole and/or laying, cutting, jointing, testing and disinfecting uPVC pipe lines in trenches. (4" (100 mm) inner dia) | | | | |
| | GROUND FLOOR | 210 | RFT | | |
| 3 | Providing and fixing C.I. floor trap 4" dia. inlet and outlet with C.I. grating floor trap of approved self cleaning design with screwed down grating with or without a vent arm with and including making requisite number of holes in walls, plinth and floor for pipe connection and making good with | | | | |
| | GROUND FLOOR | 4 | No | | |

| | | | | | |
|---|---|-----|-----|--|--|
| 4 | Providing and fixing export quality glazed earthen ware wash basin 650mm (26") Dark coloured with pedestal manufactured by international ceramics ltd ICL Boch Karm Cera or equivalent approved make with single hole chromium plated mixer tap 15mm (.5") pillar tap 2 way deluw stop cocks CI or WI bracketes 150mm (6") built in to walls 40mm (1.5") dia malleable iron or CP brass trap with malleable iron or brass union and making requistes number of hole in walls plinth and floor for pipe connections and making good with approved material including coloured glazed earthen ware pedestal manufactured by ICL/Karam Cera or approved equivalent make | | | | |
| | GROUND FLOOR | 3 | No | | |
| 5 | Providing and fixing squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC down pipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material. | | | | |
| | GROUND FLOOR | 3 | Nos | | |
| 6 | Providing and fixing European type glazed earthenware water closet ICL Ifo/Forte or approved equivalent make including cost of inlet pipe, lid cistern kit, stop cock deluxe and other accessories, fitting material such as brackets, PVC down pipe where required, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material. | | | | |
| | GROUND FLOOR | 3 | Nos | | |
| 6 | Providing and fixing chromimum plated tee stop cock 15mm (.5") of super quality of approved make | | | | |
| | GROUND FLOOR | 8 | No | | |
| 7 | Providing, laying, cutting, jointing, testing and disinfecting PPRC (1/2) dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connnections and jointing material | | | | |
| | GROUND FLOOR | 185 | RFT | | |

| | | | | | |
|----|--|---|------|--|--|
| 8 | Providing, laying, cutting, jointing, testing and disinfecting PPRC (3/4) 20mm dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connnections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |
| 9 | Providing, laying, cutting, jointing, testing and disinfecting PPRC pipe 25mm (1") i/dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |
| 10 | Providing, laying, cutting, jointing, testing and disinfecting PPRC pipe 50mm (2") i/dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connnections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |
| | | | | | |
| 11 | Providing and fixing chromimum plated bib cock 13mm 1/2" of superior quality of approved make | | | | |
| | GROUND FLOOR | 6 | No | | |
| 12 | Providing and fixing looking glass of belgium glass 600 mm x 450 mm (24" x 18") and chromimum plated screws with 3.2mm thick hard board | | | | |
| | GROUND FLOOR | 3 | Each | | |
| 13 | Providing and fixing glass shelf 600mm x 125 mm (24" x 15") with a guard rail of standerd Glass shelf of 24" x 5" size with guard rails & C.P. brackets | | | | |
| | GROUND FLOOR | 3 | No | | |
| 14 | Providing and fixing LDPE 1000 gallons capacity overhead tank manufactured by Dura or equivalent on top of any floor | | | | |
| | TOP FLOOR | 1 | No | | |

| | | | | | |
|--|--|-----|------|--|--|
| 15 | Providing and laying 4" (100 mm) inner dia Plain cement concrete pipe conforming to ASTM C-14 class-II or equivalent. moulded with cement concrete 1:1.5:3 with spigot socket or collar joint as specified in trenches to correct alignment and grade, jointing with jointing materials including cutting pipes where necessary, finishing and testing | | | | |
| | | 160 | RFT | | |
| 16 | Providing manhole type 'A' size 24" x 18" (inside dimensions) as per approved design and specifications complete for 4" to 12" dia pipes upto 4 ft. (1.2 m) depth with 16" dia. Concrete Cover fixed in 4" thick RCC 1:2:4 slab (with 5 lbs per Cu.ft. or 80 kg/Cu.m of steel), burnt brick masonry walls 9" (225 mm) thick set in 1:3 cement sand mortar, 6" thick 1:3:6 cement concrete in foundation, 4" av. thickness 1:2:4 cement concrete in benching and 1/2" (13mm) thick cement sand plaster in 1:3 to all inside wall surfaces, channels and benching including making requisite number of main and branch channels but excluding the cost of excavation, back filling and disposal of excavated stuff. | | | | |
| | | 3 | Each | | |
| 16 | Providing and fixing stainless steel sink Pakistan made Stainless steel sink 33" x 18" (825 mm x 450 mm with 1/2" (12 mm) single hole superior quality C.P. mixer of approved make r. C.I. or W.I brackets 6" built in wall, 1.5" (40 mm) rubber plug, C.P. brass chain, C.P. brass waste, pillar tap 2 way delux, 1.5" dia malleable iron or C.P. brass trap and unions and making requisite number of holes in walls, plinth and floor for pipe connections and making good with approved material. | | | | |
| | | 1 | Each | | |
| Total Amount (Inclusive of All Taxes) | | | | | |

**EMERGENCY RESPONSE CENTER MINES
DUKI RESIDENCY-1**

CIVIL WORK

| S # | DESCRIPTION | QUANTITY | UNIT | Rate Per Unit | AMOUNT |
|------------|---|-----------------|-------------|----------------------|---------------|
| 1 | DEMOLISHING | | | | |
| | Dismantling cement block masonry upto 8" width | | | | |
| | | 58.89 | | | |
| | | 88.00 | | | |
| | Total Qty | 146.89 | CFT | | |
| 2 | CONSTRUCTION | | | | |
| | Excavation in foundation of buildings and bridges including layout, dressing, refilling around structures with excavated earth, watering & ramming lead upto 100ft.(30m) & lift upto 5 ft. (1.5m) | | | | |
| | | 270.00 | CFT | | |
| 3 | Providing and laying plain hand mixed cement concrete using sand and approved source and crushed aggregate having maximum size upto 1-1/2"(38mm) & down gauge in foundation and plinth including leveling, compacting & curing. | | | | |
| | P.C.C (1:4:8) | 22.50 | CFT | | |
| 4 | Providing and laying 1:2:4 cement concrete using approved coarse sand and crushed aggregate 3/4"(19mm) and down gauge in slabs including formwork and its removal, compacting and curing | | | | |
| | Kitchen Shelf Slab | 8.00 | | | |
| | | 3.96 | | | |
| | Total Quantity | 11.96 | CFT | | |
| 5 | Providing and laying 1:3:6 cement concrete block masonry using Coarse Sand and Approved crushed aggregate 3/4" (19mm) & down gauge in foundation, basement and plinth including scaffolding, raking out joints and curing. | | | | |
| | In Foundation (step-1) | 90.00 | | | |

| | | | | | |
|----------|---|--------|------------|--|--|
| | In Foundation (step-2) | 120.00 | | | |
| | TOTAL | 210.00 | CFT | | |
| 6 | Providing and laying (1:3:6) cement concrete block masonry using Coarse Sand and Approved crushed aggregate 3/4" (19mm) and down gauge in ground floor super-structure including scaffolding, raking out joints and curing. Cement sand mortar 1 : 4 | | | | |
| | Existing gate | 16.75 | CFT | | |
| | Existing Windows | 58.96 | CFT | | |
| | Exist B-Wall up to 5' | 211.05 | CFT | | |
| | New Construction | 221.10 | CFT | | |
| | Kitchen Shelf | 10.67 | | | |
| | TOTAL | 518.53 | CFT | | |
| 7 | Providing and laying (1:3:6) cement concrete block masonry using Coarse Sand and Approved crushed aggregate 3/4" (19mm) and down gauge in ground floor super-structure including scaffolding, raking out joints and curing. Cement sand mortar 1 : 4 | | | | |
| | Partition Wall | 132.00 | CFT | | |
| 8 | 1/2 inch (13mm) thick cement plaster using Coarse Sand on walls and columns in basement, plinth and ground floor including making edges, corners and curing. | | | | |
| | Existing gate | 50 | | | |
| | Existing Windows | 176 | | | |
| | Exist B-Wall up to 5' | 630 | | | |
| | New Wall Construction | 660 | | | |
| | Partition Wall | 792 | | | |
| | | 2308 | SFT | | |
| 9 | Providing and fixing 1/4" to 3/8" (6mm to 9mm) thick Ceramic Glazed/Matt tiles (Prime Quality) of any colour and size, as directed by Engineer-in-Charge in dado/skirting in ground floor over 1/2" (13mm) thick base of cement mortar 1:3, setting of tiles in slurry of grey cement over mortar base including filling the joints and washing the tiles with whit | | | | |

| | | | | | |
|-----------|---|-------|------------|--|--|
| | ecementslurry of matching color, cleaning & curing | | | | |
| | Room Type-1(15x18) | 1080 | | | |
| | Bath Room (8x6) | 144 | | | |
| | Kitchen (8x12) | 96 | | | |
| | TOTAL | 1320 | SFT | | |
| 10 | Providingandlaying3/4"(19mm)thick mosaictiles6"x6"sizedado/skirtingofa pproveddesigninanycolor,shadeand patterninggroundfloorover3/8"thickba secementsandmortar1:3includingset tingthetileswithportlandcementslurry overcementsandjointingandwashing thetileswithcementslurryofmatchingc olorincludinggrinding,rubbing,polishi ng& mortar cost. (Skirting) | | | | |
| | Room Type-1(15x18) | 132 | | | |
| | Kitchen (8x12) | 16 | | | |
| | Total | 148 | SFT | | |
| 11 | Providingandlaying1/4"to3/8"(6mm to9mm)thickGlazed/Matttilesofanycol ourandsizeingroundfloorlaidover1"(2 5mm)thickcementsandmortarbasein cludingjointingandwashingthetileswit hwhitecementslurry of matching color by using color pigment and curing. | | | | |
| | Bath Room (8x6) Walls | 336 | | | |
| | | 252 | | | |
| | | 588 | | | |
| | D/d od Doors | 52.5 | | | |
| | Net Qtty | 535.5 | SFT | | |
| | | | | | |
| 12 | DistemperingwithBerger/IClorequiva lentsyntheticvinylemulsionpaintofap provedshadeonoldsurfaceofwallsan dceilingincludingdusting,sandpaperi ngand cleaning in basement and ground floor. | | | | |
| | Room Type-1(15x18) Short Wall | 1320 | | | |

| | | | | | |
|----|--|-----------------|------------|--|--|
| | Room Type-1(15x18) Long Wall | 1584 | | | |
| | Roof Ceiling | 1080 | | | |
| | KitchenShelf Sides | 64 | | | |
| | KitchenShelf Sides | 96 | | | |
| | Kichen Full Size Wall | 88 | | | |
| | Kichen Full Size Wall | 132 | | | |
| | Kitchen Roof Ceiling | 96 | | | |
| | Store (8x12) | 176 | | | |
| | | 264 | | | |
| | Store Roof Ceiling | 96 | | | |
| | Bath Room (8x6) Long Side | 240 | | | |
| | Bath Room (8x6) Short Side | 180 | | | |
| | Varendah wall | 489.5 | | | |
| | VarendahRoof | 534 | | | |
| | Store & Bath Out side front Wall | 214.5 | | | |
| | Store & Bath Out side Back Wall | 95.33 | | | |
| | Kitchen & Bath Out Front side Wall | 176 | | | |
| | Kitchen & Bath Out Back side Wall | 95.33 | | | |
| | Boundary Wall Long | 1,386.00 | | | |
| | Boundary Wall Short | 407.00 | | | |
| | Total Quantity | 8,813.67 | | | |
| | D/d of Doors & Windows | | | | |
| | W1 | 176 | | | |
| | W2 | 40 | | | |
| | D1 | 196 | | | |
| | D2 | 175 | | | |
| | Total Deduction | 587.00 | | | |
| | Net Quantity | 8,226.67 | SFT | | |
| 13 | PaintingwithICI/Bergerorequivalents uperglosssyntheticenamelpaintintwo or morecoatsaspermanufacturer's instructions onwoodworkoverandincludingthecostofprimingcoat,surfacepreparation,rubbingdownsmooth,knotted ,fillingcracks,holesandjointsinground floororbasement. (@atleast1.65Litre per10Sq.m) | | | | |
| | Room Type-1(15x18) Short Wall | 1320 | | | |
| | Room Type-1(15x18) Long Wall | 1584 | | | |
| | Roof Ceiling | 1080 | | | |
| | KitchenShelf Sides | 64 | | | |
| | KitchenShelf Sides | 96 | | | |
| | Kichen Full Size Wall | 88 | | | |

| | | | | | |
|----|---|-----------------|------------|--|--|
| | Kichen Full Size Wall | 132 | | | |
| | Kitchen Roof Ceiling | 96 | | | |
| | Store (8x12) | 176 | | | |
| | | 264 | | | |
| | Store Roof Ceiling | 96 | | | |
| | Bath Room (8x6) Long Side | 240 | | | |
| | Bath Room (8x6) Short Side | 180 | | | |
| | Total Quantity | 5,416.00 | | | |
| | D/d of Doors & Windows | | | | |
| | W1 | 176 | | | |
| | W2 | 40 | | | |
| | D1 | 196 | | | |
| | D2 | 87.5 | | | |
| | Total Deduction | 499.50 | | | |
| | Net Quantity | 4,916.50 | SFT | | |
| | | | | | |
| 14 | Applying weather resistant paint coat in gsuchasICI/Bergerorequivalentpaint ofapprovedshadeonoldsurfaceofwall sandceilingincludingdusting,sandpa peringand cleaning, scaffolding and removal of debris. | | | | |
| | Store & Bath Out side front Wall | 214.5 | | | |
| | Store & Bath Out side Back Wall | 95.33 | | | |
| | Kitchen & Bath Out Front side Wall | 176 | | | |
| | Kitchen & Bath Out Back side Wall | 95.33 | | | |
| | Boundary Wall Long | 1,386.00 | | | |
| | Boundary Wall Short | 407.00 | | | |
| | Total Quantity | 2,374.17 | SFT | | |
| 15 | Providingandfixingmouldedsteeldoor frameofapprovedprofile,manufacture dfromzinc- coatedmildsteelsheets16gaugemad ebyShahahIndustriesorequivalentst andardconformingtoB.S.S.1245,trea tedwithspecialprimerbasepaintallrou nd,fittedwithsixfixinglugs,threesteelh ingesforfixingdoorshuttersstandardlo ck- strikeplate,oneslidingholteye,andthr eerubberbuffers,includingcuttinghole sandmakinggooddamagestowallsan dfillingthedoormapcavitywithleance mentmortar1:4asdirectedbytheEngin eer Incharge. | | | | |

| | | | | | |
|-----------|--|-------|------------|--|--|
| | D1 (3.5+3.5+7+7) | 84 | | | |
| | D2 (2.5+2.5+7+7) | 95 | | | |
| | Total Quantity | 179 | RFT | | |
| 16 | Providing and fixing 1.5" (38mm) thick pressed veneered door shutters fully flushed with First class wood veneering on all faces and sides fixed over partal wood cavited core and framework of not less than 4" (100mm) wide strips all round with approved iron hinges, tower bolts as required. | | | | |
| | D1 | 98 | | | |
| | D2 | 87.5 | | | |
| | Kitchen Shelf | 30 | | | |
| | Total Quantity | 215.5 | SFT | | |
| 17 | Providing and fixing locks with brass or specially supplied screws including Door Closers and Floor Hinges of approved design including cutting wood to required shape and size with two operating keys. | | | | |
| | Hyundi lock | | | | |
| 18 | Providing and laying 1" (25mm) thick super white marble slab exceeding 12"x12" size kitchen top in white cement including all labour for grinding and polishing | | | | |
| | Kitchen Shelf | 24 | | | |
| | | 12 | | | |
| | Total Quantity | 36 | SFT | | |
| 19 | Providing and fixing hot dipped galvanized fully glazed double leaf hung steel windows and ventilators of approved section with Z-section 1.25" (32mm) width at each edge including using approved brass section oxidized fitting, iron lugs, cutting hole and making good the damages to walls. | | | | |
| | W1 | 132 | | | |
| | W2 | 20 | | | |
| | V1 | 12 | | | |
| | | 164 | SFT | | |

| | | | | | |
|----|--|------|-----|--|--|
| 20 | Providing and fixing steel grated double leaf door with locking arrangement, angle iron 2"x2"x3/8" frame, middle strip, 1/4" thick gusset plate 3"x3" at each edge and 3/4" M.S. square or round bars at 4" c/c including two coats of red oxide paint | | | | |
| | | 28 | SFT | | |
| 21 | Providing and installation of tuff tile | 1400 | SFT | | |
| 22 | Providing underground RCC circular water tank of dia 6ft and depth 8ft | 1 | | | |
| | Total Amount (Inclusive of All Taxes) | | | | |

**EMERGENCY RESPONSE CENTER MINES
DUKI RESIDENCY-1**

ELECTRICAL WORKS

| S. No | DESCRIPTION OF ITEMS | QUANTITY | UNIT | RATE (RS) | AMOUNT (RS) |
|-------|--|----------|-------|-----------|-------------|
| 1 | Concealed / open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables, (Concealed wiring with 3/4" 20 (mm) dia. PVC conduit and accessories such as bends, elbows, junction boxes etc.) | | | | |
| | Room (4x4)+(2x3)+3)+4 | 32 | Point | | |
| 2 | Concealed/open wiring for 5 Amp. Socket outlets from nearest available circuit with a length upto 20 ft. (6m) with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables. (Concealed wiring with 3/4" -20 mm) dia. PVC conduit and accessories such as bends, elbows, junction boxes etc) | | | | |
| | | 6 | Point | | |
| 3 | Provide, install, test and commission recessed wall mounting type distribution board fabricated from 16SWG steel sheet, powder coated with approved color 2'x2'x1.5' | | | | |

| | | | | | |
|--|--|----|------|--|--|
| | | 1 | Each | | |
| 4 | Supply ,Installing ,Connection of 2 Pole Circuit Breaker 50 Ampere | | | | |
| | | 5 | Each | | |
| 5 | Single Pole Circuit Breaker 16 Ampere | | | | |
| 6 | Supply and install Energy Saver electric bulbs | | | | |
| | | 25 | No's | | |
| 7 | Supply and install 40W electric tube light rod including patty | | | | |
| | | 7 | No's | | |
| 8 | Supply and install 10" (250 mm) sweep exhaust fan including plastic louvers. | | | | |
| | | 1 | No's | | |
| 9 | Supplyandinstall56"(1.42m)sweepceilingfanwithfan hookanddimmercomplete with all accessories. | | | | |
| | | 6 | No's | | |
| Total Amount (Inclusive of All Taxes) | | | | | |

**EMERGENCY RESPONSE CENTER MINES
DUKI RESIDENCY-1**

PLUMBING WORKS

| S. No | DESCRIPTION OF ITEMS | QUANTIT Y | UNIT | RAT E (RS) | AMOUNT (RS) |
|-------|---|-----------|------|------------|-------------|
| 1 | Providing and Installing uPVC blind pipe of approved make registered with PSQCA in tubewell bore hole and/or laying, cutting, jointing, testing and disinfecting uPVC pipe lines in trenches. (3" (75 mm) inner dia) | | | | |
| | GROUND FLOOR | 60 | RFT | | |
| 2 | Providing and Installing uPVC blind pipe of approved make registered with PSQCA in tubewell bore hole and/or laying, cutting, jointing, testing and disinfecting uPVC pipe lines in trenches. (4" (100 mm) inner dia) | | | | |
| | GROUND FLOOR | 210 | RFT | | |
| 3 | Providing and fixing C.I. floor trap 4" dia. inlet and outlet with C.I. grating floor trap of approved self cleaning design with screwed down grating with or without a vent arm with and including making requisite number of holes in walls, plinth and floor for pipe connection and making good with | | | | |
| | GROUND FLOOR | 4 | No | | |

| | | | | | |
|---|---|-----|-----|--|--|
| 4 | Providing and fixing export quality glazed earthen ware wash basin 650mm (26") Dark coloured with pedestal manufactured by international ceramics ltd ICL Boch Karm Cera or equivalent approved make with single hole chromium plated mixer tap 15mm (.5") pillar tap 2 way deluw stop cocks CI or WI bracketes 150mm (6") built in to walls 40mm (1.5") dia malleable iron or CP brass trap with malleable iron or brass union and making requistes number of hole in walls plinth and floor for pipe connections and making good with approved material including coloured glazed earthen ware pedestal manufactured by ICL/Karam Cera or approved equivalent make | | | | |
| | GROUND FLOOR | 3 | No | | |
| 5 | Providing and fixing squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC down pipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material. | | | | |
| | GROUND FLOOR | 3 | Nos | | |
| 6 | Providing and fixing European type glazed earthenware water closet ICL Ifo/Forte or approved equivalent make including cost of inlet pipe, lid cistern kit, stop cock deluxe and other accessories, fitting material such as brackets, PVC down pipe where required, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material. | | | | |
| A | GROUND FLOOR | 3 | Nos | | |
| 6 | Providing and fixing chromimum plated tee stop cock 15mm (.5") of super quality of approved make | | | | |
| | GROUND FLOOR | 8 | No | | |
| 7 | Providing, laying, cutting, jointing, testing and disinfecting PPRC (1/2) dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material | | | | |
| | GROUND FLOOR | 185 | RFT | | |
| 8 | Providing, laying, cutting, jointing, testing and disinfecting PPRC (3/4) 20mm dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connnections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |
| 9 | Providing, laying, cutting, jointing, testing and disinfecting PPRC pipe 25mm (1") i/dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connnections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |

| | | | | | |
|----|--|-----|------|--|--|
| 10 | Providing, laying, cutting, jointing, testing and disinfecting PPRC pipe 50mm (2") i/dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |
| 11 | Providing and fixing chromimum plated bib cock 13mm 1/2" of superior quality of approved make | | | | |
| | GROUND FLOOR | 6 | No | | |
| 12 | Providing and fixing looking glass of belgium glass 600 mm x 450 mm (24" x 18") and chromimum plated screws with 3.2mm thick hard board | | | | |
| | GROUND FLOOR | 3 | Each | | |
| 13 | Providing and fixing glass shelf 600mm x 125 mm (24" x 15") with a guard rail of standerd Glass shelf of 24" x 5" size with guard rails & C.P. brackets | | | | |
| | GROUND FLOOR | 3 | No | | |
| 14 | Providing and fixing LDPE 1000 gallons capacity overhead tank manufactured by Dura or equivalent on top of any floor | | | | |
| | TOP FLOOR | 1 | No | | |
| 15 | Providing and laying 4" (100 mm) inner dia Plain cement concrete pipe conforming to ASTM C-14 class-II or equivalent. moulded with cement concrete 1:1.5:3 with spigot socket or collar joint as specified in trenches to correct alignment and grade, jointing with jointing materials including cutting pipes where necessary, finishing and testing | | | | |
| | | 160 | RFT | | |
| 16 | Providing manhole type 'A' size 24" x 18" (inside dimensions) as per approved design and specifications complete for 4" to 12" dia pipes upto 4 ft. (1.2 m) depth with 16" dia. Concrete Cover fixed in 4" thick RCC 1:2:4 slab (with 5 lbs per Cu.ft. or 80 kg/Cu.m of steel), burnt brick masonry walls 9" (225 mm) thick set in 1:3 cement sand mortar, 6" thick 1:3:6 cement concrete in foundation, 4" av. thickness 1:2:4 cement concrete in benching and 1/2" (13mm) thick cement sand plaster in 1:3 to all inside wall surfaces, channels and benching including making requisite number of main and branch channels but excluding the cost of excavation, back filling and disposal of excavated stuff. | | | | |
| | | 3 | Each | | |

| | | | | | |
|----|---|--|------|--|--|
| 17 | Providing and fixing stainless steel sink Pakistan made Stainless steel sink 33" x 18" (825 mm x 450 mm with 1/2" (12 mm) single hole superior quality C.P. mixer of approved make r. C.I. or W.I brackets 6" built in wall, 1.5" (40 mm) rubber plug, C.P. brass chain, C.P. brass waste, pillar tap 2 way delux, 1.5" dia malleable iron or C.P. brass trap and unions and making requisite number of holes in walls, plinth and floor for pipe connections and making good with approved material. | | | | |
| | | 1 | Each | | |
| | | Total Amount (Inclusive of All Taxes) | | | |

**EMERGENCY RESPONSE CENTER
DUKI RESIDENCY-2**

CIVIL WORK

| S# | DESCRIPTION | QUANTITY | UNIT | RATE/ UNIT | AMOUNT |
|----|--|----------|------|---------------|--------|
| 1 | Distempering with Berger/ICI or equivalent synthetic vinyl emulsion paint of approved shade on old surface of walls and ceiling including dusting, sandpapering and cleaning in basement and ground floor. | | | | |
| | Room Type-1(15x18) Short Wall | 1320 | | | |
| | Room Type-1(15x18) Long Wall | 1584 | | | |
| | Roof Ceiling | 1080 | | | |
| | Kitchen Shelf Sides | 80 | | | |
| | Kitchen Shelf front Sides | 120 | | | |
| | Kitchen Full short Wall | 80 | | | |
| | Kitchen Full Size Wall | 80 | | | |
| | Kitchen Roof Ceiling | 96 | | | |
| | Store short (8x12) | 176 | | | |
| | Store long (8x12) | 264 | | | |
| | Store Roof Ceiling | 96 | | | |
| | Bath Room (8x6) Long Side | 240 | | | |
| | Bath Room (8x6) Short Side | 180 | | | |
| | Varendah wall | 489.5 | | | |

| | | | | | |
|----------|--|-----------------|------------|--|--|
| | VarendahRoof | 534 | | | |
| | Store & Bath Out side front Wall | 214.5 | | | |
| | Store & Bath Out side Back Wall | 95.33 | | | |
| | Kitchen & Bath Out Front side Wall | 286 | | | |
| | Kitchen & Bath Out Back side Wall | 95.33 | | | |
| | Boundary Wall Long | 1,386.00 | | | |
| | Boundary Wall Short | 407.00 | | | |
| | Total Quantity | 8,903.67 | | | |
| | D/d of Doors & Windows | | | | |
| | W1 | 176 | | | |
| | W2 | 40 | | | |
| | D1 | 196 | | | |
| | D2 | 175 | | | |
| | Total Deduction | 587.00 | | | |
| | Net Quantity | 8,316.67 | SFT | | |
| 2 | Providingandfixingmouldedsteeldoor frameofapprovedprofile,manufacture dfromzinc-coatedmildsteelsheets16gaugemade byShahahIndustriesorequivalentstandardconformingtoB.S.S.1245,treated withspecialprimerbasepaintallround,f ittedwithsixfixinglugs,threesteelhinge sforfixingdoorshuttersstandardlock-strikeplate,oneslidingholteye,andthre erubberbuffers,includingcuttingholes andmakinggooddamageto wallsandf illingthedoorframecavitywithleancem entmortar1:4asdirectedbytheEngine er Incharge. | | | | |
| | D1 (3.5+3.5+7+7) | 84 | | | |
| | D2 (2.5+2.5+7+7) | 95 | | | |
| | Total Quantity | 179 | RFT | | |
| 3 | Providingandfixing1.5"(38mm)thickp ressedveneereddoorshuttersfullyflus hedwithFirstclasswoodveneeringona llfacesandsidesfixedoverpartalwoodc avitedcoreandframeworkofnotlessth an4"(100mm)widestripsallround with approved iron hinges, tower bolts as required. | | | | |

| | | | | | |
|--|---|-------|-----|--|--|
| | D1 | 98 | | | |
| | D2 | 87.5 | | | |
| | Kitchen Shelf | 30 | | | |
| | Total Quantity | 215.5 | SFT | | |
| 4 | Providing and fixing locks with brassors pecially supplied screws including Door Closers and Floor Hinges of approved design including cutting wood to required shape and size with two operating keys. | | | | |
| | Hyundi lock | 9 | | | |
| Total Amount (Inclusive of All Taxes) | | | | | |

**EMERGENCY RESPONSE CENTER
DUKI RESIDENCY-2**

ELECTRICAL WORKS

| S. No | DESCRIPTION OF ITEMS | QUANTITY | UNIT | RATE (RS) | AMOUNT (RS) |
|--------------|--|-----------------|-------------|------------------|--------------------|
| 1 | Concealed / open wiring from point to switch with length upto 30 ft. (10m) including any switch to switch wiring with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables, (Concealed wiring with 3/4" 20 (mm) dia. PVC conduit and accessories such as bends, elbows, junction boxes etc.) | | | | |
| | Room (4x4)+(2x3)+3)+4 | 32 | Point | | |
| 2 | Concealed/open wiring for 5 Amp. Socket outlets from nearest available circuit with a length upto 20 ft. (6m) with 3x1.5 Sq.mm PVC insulated single core copper conductor Pakistan Cables, Pioneer, Newage or approved equivalent cables. (Concealed wiring with 3/4" -20 mm) dia. PVC conduit and accessories such as bends, elbows, junction boxes etc) | | | | |
| | | 6 | Point | | |
| 3 | Provide, install, test and commission recessed wall mounting type distribution board fabricated from 16SWG steel sheet, powder coated with approved color 2'x2'x1.5' | | | | |
| | | 1 | Each | | |

| | | | | | |
|--|---|----|------|--|--|
| 4 | Supply ,Installing ,Connection of 2 Pole Circuit Breaker 50 Ampere | | | | |
| | | 5 | Each | | |
| 5 | Single Pole Circuit Breaker 16 Ampere | | | | |
| 6 | Supply and install Energy Saver electric bulbs | | | | |
| | | 25 | No's | | |
| 7 | Supply and install 40W electric tube light rod including patty | | | | |
| | | 7 | No's | | |
| 8 | Supply and install 10" (250 mm) sweep exhaust fan including plastic louvers. | | | | |
| | | 1 | No's | | |
| 9 | Supplyandinstall56"(1.42m)sweepceilingfanwithfanhookanddimmercomplete with all accessories. | | | | |
| | | 6 | No's | | |
| Total Amount (Inclusive of All Taxes) | | | | | |

**EMERGENCY RESPONSE CENTER
DUKI RESIDENCY-2**

PLUMBING WORKS

| S. No | DESCRIPTION OF ITEMS | QUANTITY | UNIT | RATE (RS) | AMOUNT (RS) |
|-------|---|----------|------|-----------|-------------|
| 1 | Providing and Installing uPVC blind pipe of approved make registered with PSQCA in tubewell bore hole and/or laying, cutting, jointing, testing and disinfecting uPVC pipe lines in trenches. (3" (75 mm) inner dia) | | | | |
| | GROUND FLOOR | 60 | RFT | | |
| 2 | Providing and Installing uPVC blind pipe of approved make registered with PSQCA in tubewell bore hole and/or laying, cutting, jointing, testing and disinfecting uPVC pipe lines in trenches. (4" (100 mm) inner dia) | | | | |
| | GROUND FLOOR | 210 | RFT | | |

| | | | | | |
|---|---|---|-----|-----------|-----------|
| 3 | Providing and fixing C.I. floor trap 4" dia. inlet and outlet with C.I. grating floor trap of approved self cleaning design with screwed down grating with or without a vent arm with and including making requisite number of holes in walls, plinth and floor for pipe connection and making good with | | | | |
| | GROUND FLOOR | 4 | No | | |
| 4 | Providing and fixing export quality glazed earthen ware wash basin 650mm (26") Dark coloured with pedestal manufactured by international ceramics ltd ICL Boch Karm Cera or equivalent approved make with single hole chromium plated mixer tap 15mm (.5") pillar tap 2 way deluw stop cocks CI or WI bracketes 150mm (6") built in to walls 40mm (1.5") dia malleable iron or CP brass trap with malleable iron or brass union and making requistes number of hole in walls plinth and floor for pipe connections and making good with approved material including coloured glazed earthen ware pedestal manufactured by ICL/Karam Cera or approved equivalent make | | | | |
| | GROUND FLOOR | 3 | No | 15,440.40 | 46,321.20 |
| 5 | Providing and fixing squatting type water closet with integral treads ICL Boch/Karam Cera or approved equivalent make including cost of inlet pipe cistern and lid cistern kit, stop cock deluxe type and other accessories, fittings, brackets, PVC down pipe, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material. | | | | |
| | GROUND FLOOR | 3 | Nos | 15,253.99 | 45,761.97 |
| 6 | Providing and fixing European type glazed earthenware water closet ICL Ifo/Forte or approved equivalent make including cost of inlet pipe, lid cistern kit, stop cock deluxe and other accessories, fitting material such as brackets, PVC down pipe where required, rubber rings/washers, making requisite number of holes in walls, plinth and floor for pipe connection and making good with approved material. | | | | |
| A | GROUND FLOOR | 3 | Nos | | |

| | | | | | |
|----|---|-----|------|--|--|
| 6 | Providing and fixing chromimum plated tee stop cock 15mm (.5") of super quality of approved make | | | | |
| | GROUND FLOOR | 8 | No | | |
| 7 | Providing, laying, cutting, jointing, testing and disinfecting PPRC (1/2) dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material | | | | |
| | GROUND FLOOR | 185 | RFT | | |
| 8 | Providing, laying, cutting, jointing, testing and disinfecting PPRC (3/4) 20mm dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |
| 9 | Providing, laying, cutting, jointing, testing and disinfecting PPRC pipe 25mm (1") i/dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |
| 10 | Providing, laying, cutting, jointing, testing and disinfecting PPRC pipe 50mm (2") i/dia pipes confirming to ISO 4427, PN-20, complete in all respects with specials and valves etc. including all fittings, connections and jointing material | | | | |
| | GROUND FLOOR | 0 | RFT | | |
| | | | | | |
| 11 | Providing and fixing chromimum plated bib cock 13mm 1/2" of superior quality of approved make | | | | |
| | GROUND FLOOR | 6 | No | | |
| 12 | Providing and fixing looking glass of belgium glass 600 mm x 450 mm (24" x 18") and chromimum plated screws with 3.2mm thick hard board | | | | |
| | GROUND FLOOR | 3 | Each | | |
| 13 | Providing and fixing glass shelf 600mm x 125 mm (24" x 15") with a guard rail of standerd Glass shelf of 24" x 5" size with guard rails & C.P. brackets | | | | |
| | GROUND FLOOR | 3 | No | | |

| | | | | | |
|----|--|--|------|--|--|
| 14 | Providing and fixing LDPE 1000 gallons capacity overhead tank manufactured by Dura or equivalent on top of any floor | | | | |
| | TOP FLOOR | 1 | No | | |
| 15 | Providing and laying 4" (100 mm) inner dia Plain cement concrete pipe conforming to ASTM C-14 class-II or equivalent. moulded with cement concrete 1:1.5:3 with spigot socket or collar joint as specified in trenches to correct alignment and grade, jointing with jointing materials including cutting pipes where necessary, finishing and testing | | | | |
| | | 160 | RFT | | |
| 16 | Providing manhole type 'A' size 24" x 18" (inside dimensions) as per approved design and specifications complete for 4" to 12" dia pipes upto 4 ft. (1.2 m) depth with 16" dia. Concrete Cover fixed in 4" thick RCC 1:2:4 slab (with 5 lbs per Cu.ft. or 80 kg/Cu.m of steel), burnt brick masonry walls 9" (225 mm) thick set in 1:3 cement sand mortar, 6" thick 1:3:6 cement concrete in foundation, 4" av. thickness 1:2:4 cement concrete in benching and 1/2" (13mm) thick cement sand plaster in 1:3 to all inside wall surfaces, channels and benching including making requisite number of main and branch channels but excluding the cost of excavation, back filling and disposal of excavated stuff. | | | | |
| | | 3 | Each | | |
| 17 | Providing and fixing stainless steel sink Pakistan made Stainless steel sink 33" x 18" (825 mm x 450 mm with 1/2" (12 mm) single hole superior quality C.P. mixer of approved make r. C.I. or W.I brackets 6" built in wall, 1.5" (40 mm) rubber plug, C.P. brass chain, C.P. brass waste, pillar tap 2 way delux, 1.5" dia malleable iron or C.P. brass trap and unions and making requisite number of holes in walls, plinth and floor for pipe connections and making good with approved material. | | | | |
| | | 1 | Each | | |
| | | Total Amount (Inclusive of All Taxes) | | | |

DECLARATION BY THE BIDDER

I solemnly undertake that:

- a. Having read, understood & made myself aware of all the Terms & conditions mentioned in this Bidding Document & the Rules, Regulations & Policies of the Government of Balochistan, governing the procurement & financial matters, **AGREE, ACCEPT & UNDETAKES TO ABIDE BY THE SAME.**
- b. The information provided in this form is correct to the best of my knowledge & in the event of change; details will be provided as soon as possible

Name & Designation _____

Signature _____ Date _____

Company stamp _____